

LANDSCAPING SCHEDULE

ROUTE	STATION TO STATION		LT / RT	21101615	25000110	25000210	25000310	25000400	25000500	25000600	25000750	25000775	25100125	25100630	25100900	28000250	X2501750
				TOPSOIL FURNISH AND PLACE, 4"	SEEDING, CLASS 1A	SEEDING, CLASS 2A	SEEDING, CLASS 4	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MOWING	SELECTIVE MOWING STAKES	MULCH, METHOD 3	EROSION CONTROL BLANKET	TURF REINFORCEMENT MAT	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 4, (SPECIAL)
				SQ YD	ACRE	ACRE	ACRE	POUND	POUND	POUND	ACRE	EACH	ACRE	SQ YD	SQ YD	POUND	ACRE
US 52	12+00	16+00	LT	1203.1	0.04	0.21	0.04	31.5	31.5	31.5	0.25	3	0.38	1620.8	118.2	38.0	0.09
US 52	12+00	16+00	RT	913.3		0.14	0.01	13.5	13.5	13.5	0.14		0.15	913.3		15.0	
US 52	16+00	22+00	LT	2677.3		0.49	0.06	61.2	61.2	61.2	0.49	5	0.68	3309.1		68.0	0.13
US 52	16+00	22+00	RT	2435.7		0.44	0.06	48.6	48.6	48.6	0.44		0.54	2621.4		54.0	0.04
US 52	22+00	28+00	LT	4119.7		0.68	0.17	89.1	89.1	89.1	0.68	6	0.99	4780.2		99.0	0.14
US 52	22+00	28+00	RT	4278.3		0.70	0.18	92.7	92.7	92.7	0.70		1.03	4993.1		103.0	0.15
US 52	28+00	29+64	LT	941.1		0.18	0.02	24.3	24.3	24.3	0.18	1	0.26	1212.2		26.0	0.06
US 52	28+00	29+64	RT	987.9		0.19	0.02	26.1	26.1	26.1	0.19	1	0.25	1193.0		25.0	0.04
	29+64	30+10	LT	73.5	0.02						0.02		0.02	73.5		2.0	
	29+64	30+10	RT	235.6	0.05						0.05		0.05	235.6	28.5	5.0	
N BROOKVILLE RD	197+75	198+10	LT/RT	162.8		0.03	0.01	5.4	5.4	5.4	0.03	2	0.06	243.7		6.0	0.02
W CHAMBERS RD	298+35	299+75	LT/RT	336.9	0.03	0.03	0.01	6.3	6.3	6.3	0.06		0.07	336.9		7.0	
TOTALS				18365.2	0.14	3.09	0.58	398.7	398.7	398.7	3.23	18	4.48	21532.8	146.7	448.0	0.67
ROUNDED TOTALS				18366	0.25	3.25	0.75	450	450	450	3.50		5.00	24200	147	500	0.75

PERMANENT PAVEMENT MARKINGS AND GROOVING SCHEDULE

STATION TO STATION		LT/RT	78009004	78009024	78011025	78011125
			MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	GROOVING FOR RECESSED PAVEMENT MARKING 5"	GROOVING FOR RECESSED PAVEMENT MARKING 25"
			FOOT	FOOT	FOOT	FOOT
11+90	18+59.47	LT	669.5		669.5	
11+90	14+49.33	RT	259.3		259.3	
15+88.03	19+61.75	RT	373.7		373.7	
20+30.61	29+74	LT	943.4		943.4	
21+07.17	29+74	RT	866.8		866.8	
11+90	20+45	CL	855.0		855.0	
27+60	29+74	CL	214.0		214.0	
11+90	29+74	CL	443.5		443.5	
W YOUNG ST	1000+31	RT		26		13
N BROOKVILLE RD	197+41	LT		30		15
W CHAMBERS ST	299+64	RT		28		14
TOTALS			4625.2	84	4625.2	42
ROUNDED TOTALS			4626	84*	4626	42

TEMPORARY DITCH CHECKS SCHEDULE

ROUTE	STATION TO STATION	LT/RT	HEIGHT (FT)	SPACING (FT)	NUMBER OF DITCH CHECKS	28000305
						TEMPORARY DITCH CHECKS
						FOOT
US 52	12+00 - 18+80	LT	2.0	40	17	136
US 52	12+00 - 13+20	RT	1.5	30	4	32
US 52	13+83 - 14+53	RT	1.5	40	2	16
US 52	15+50 - 19+25	RT	1.5	75	6	48
US 52	20+25 - 25+00	LT	1.5	150	4	32
US 52	20+60 - 25+00	RT	1.5	150	4	32
US 52	26+00 - 29+50	RT	1.5	150	3	24
US 52	26+00 - 29+25	LT	1.5	150	3	24
W YOUNG ST	1000+40 - 1001+00	LT	1.5	50	1	8
BROOKVILLE RD	197+80 - 198+10	LT	1.5	30	1	8
BROOKVILLE RD	197+40 - 198+10	RT	1.5	40	1	8
W CHAMBERS RD	298+35 - 299+40	LT	1.5	50	1	8
TOTAL						376

TEMPORARY PAVEMENT MARKINGS SCHEDULE

ROUTE	STATION TO STATION		LT/RT	70300100	70300150
				SHORT TERM PAVEMENT MARKING	SHORT TERM PAVEMENT MARKING REMOVAL
			FOOT	SQ FT	
US 52	12+00	29+64	CL	176.4	59.9
TOTALS			176.4	59.9	
ROUNDED TOTALS			180	60	

EXPLORATION TRENCH SCHEDULE

ROUTE	STATION TO STATION		LT / RT	21301052	61133100	61133200	61133300	61133400
				EXPLORATION TRENCH 52" DEPTH	FIELD TILE JUNCTION VAULTS, 2' DIA	FIELD TILE JUNCTION VAULTS, 3' DIA	FIELD TILE JUNCTION VAULTS, 4' DIA	FIELD TILE JUNCTION VAULTS, 5' DIA
			FOOT	EACH	EACH	EACH	EACH	
US 52	21+00	29+00	LT	800	1	1	1	1
US 52	21+00	29+00	RT	800	1	1	1	1
TOTALS			1600	2	2	2	2	

MODEL: Default; FILE NAME: P:\C\proj\DOT_DIST\DOT_2_PTE_190-22_various_P1_1_and_P2_sub_to_BFMWVO_6_US_52_over_Elkhorn_Creek_3119007-06_CAD_Sheets\0264857-ent-ech.dgn

The Upchurch Group
architects engineers surveyors
Professional Design Firm Corporation
123 North 15th Street
Mason, IL 61938
Phone: 217.255.5177
License No. 194-003401
e-mail: upchurchgroup@upchurchgroup.com

USER NAME = Sta42	DESIGNED - SJF	REVISED -
TUG PROJECT NO. 3119007-06	DRAWN -	REVISED -
PLOT SCALE = 40.0000 ' / in.	CHECKED - SJF	REVISED -
PLOT DATE = 6/22/2022	DATE - JUNE 22, 2022	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**US ROUTE 52 OVER ELKHORN CREEK
SCHEDULE OF QUANTITIES**

SCALE: 40.0000 ' / in. SHEET OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2079	16BR-1	OGLE	130	19
CONTRACT NO. 64H57			ILLINOIS FED. AID PROJECT	