	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE LANDSCAPING 90% FED 10% STATE 0031 URBAN	CONSTRUCTION CODE LANDSCAPING 0% FED 100% STATE 0031 URBAN
	28000510	INLET FILTERS	EACH	10	10	
	31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	36	36	
	31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	194	194	
	31101810	SUBBASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	55	55	
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	194	194	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	36	36	
	50300225	CONCRETE STRUCTURES	CU YD	50.4	50.4	
	50300254	RUBBED FINISH	SQ FT	1,328	1,328	
	50300300	PROTECTIVE COAT	SQ YD	249	249	
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5,090	5,090	
	60107600	PIPE UNDERDRAINS 4"	FOOT	130	130	
	60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1200	1200	
*	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4	
1	~~67000400~~	~~ENGINEER'S FIELD OFFICE, TYPE A~~	~~CAL MO~~	~~34~~	~~34~~	
	67100100	MOBILIZATION	L SUM	1	1	

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICPATING ITEM

1 Rev. 11-7-14

Rev.

TranSystems

D160X62-sht-500.dgn	DESIGNED - JLV	REVISED -
USER NAME = BAWitort	DRAWN - BAW	REVISED -
PLOT SCALE = 20.0000 ' / in.	CHECKED - JMG	REVISED -
PLOT DATE = 8/19/2014	DATE - 8/20/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET 2 OF 6 SHEETS | STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-0741	COOK	58	5

CONTRACT NO. 60X62

ILLINOIS FED. AID PROJECT

FILE PATH = pw:\\388839-pwint1.eecomail.net:local\PWAFFDMS01\Documents\81 Americas\Transportation\69269958 Circle\Phase II\D160 CAD\006 Roadway\Sheets\69262_Contract\D160X62-sht-500.dgn