


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN	
				CONST. CODE	CONST. CODE
				80% FED 20% STATE	80% FED 20% STATE
				ROADWAY	BRIDGE
				0004	0011
				RURAL	S.N. 098-0015
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	2,319.0	2,319.0	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	4,691	4,691	
60623200	CONCRETE MEDIAN, TYPE SM-6.24	SO FT	4,596	4,596	
+ 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	196	196	
+ 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	
+ 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3	
+ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	205	205	
+ 63500105	DELINEATORS	EACH	2	2	
63800920	MODULAR GLARE SCREEN SYSTEM, TEMPORARY	FOOT	401	401	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	
67100100	MOBILIZATION	L SUM	1	1	
70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	1	1	

+ SPECIALTY ITEM

FILE NAME : n:\p1\6308-6349\6346\B25\micro\101\026417-01-500.dgn



1170 SOUTH HOUBOLT ROAD  
JOLIET, ILLINOIS 60431  
(815) 744-4200

USER NAME	brianf	DESIGNED	VLF	REVISED	-
		DRAWN	DJW	REVISED	-
		CHECKED	MAG	REVISED	-
		DATE	8-14-14	REVISED	-

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: N/A    SHEET 5 OF 9 SHEETS    STA.    TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	101 BR-3	WHITESIDE	130	9
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64C17	