

GENERAL NOTES (CONTINUED)

THE CONTRACTOR SHALL BEGIN FENCE ERECTION AS SOON AS CLEARING OPERATIONS PERMIT. THE ENGINEER SHALL CONTACT THE LAND OWNERS THREE WEEKS PRIOR TO REMOVING THE EXISTING FENCE. PHONE NUMBERS FOR THE PROPERTY OWNERS CAN BE OBTAINED THROUGH THE IDOT LAND ACQUISITION DEPARTMENT. BEFORE REMOVING EXISTING FENCE FROM AN AREA THAT CONTAINS LIVESTOCK, THE CONTRACTOR SHALL ERECT WOVEN WIRE FENCE, 4', AT THE LOCATION SHOWN IN THE PLANS. THE CONTRACTOR SHALL CONCENTRATE HIS PERMANENT FENCING OPERATIONS AT THESE LOCATIONS AND AT OTHER SPECIFIC LOCATIONS AS DIRECTED BY THE ENGINEER. THE COST OF ARRANGING WORK AS HEREIN SPECIFIED WILL NOT BE PAID FOR AS A SEPARATE ITEM BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER FOOT FOR WOVEN WIRE FENCE, 4'.

TREE PLANTING LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT. MULCH SHALL BE PLACED 4" THICK AND TO THE DIAMETER AROUND THE TREE AS SHOWN ON DISTRICT STANDARD 92.1. THE MULCH SHALL BE HARDWOOD WOOD CHIPS PLACED ON WEED BARRIER FABRIC. THIS WORK SHALL BE INCLUDED IN THE COST OF THE TREE.

RIGHT-OF-WAY MARKERS WILL BE ERECTED PER HIGHWAY STANDARD 666001 WITH THE BACK FACE OF THE MARKER ON THE RIGHT-OF-WAY LINE, UNLESS THE NEW RIGHT-OF-WAY LINE HAS BEEN SURVEYED AND PINNED, IN WHICH INSTANCE THE RIGHT OF WAY MARKERS WILL BE ERECTED 12 INCHES INSIDE THE NEW RIGHT-OF-WAY LINE. THE METHOD OF INSTALLATION SHALL BE APPROVED BY THE ENGINEER.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON- EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING LISTED UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS ARE MEMBERS OF JULIE:

COMMONWEALTH EDISON, 123 ENERGY AVENUE, ROCKFORD, IL 61109
 NICOR GAS CO., 1844 FERRY ROAD, NAPERVILLE, IL 60563-9600
 FRONTIER LEGACY, 124 EAST LINCOLNWAY, MORRISON, IL 61270

IDOT IS NOT A MEMBER OF JULIE. IF YOU ARE NEAR ANY OVERHEAD LIGHTING, INTERSECTION LIGHTING OR TRAFFIC SIGNALS, CONTACT THE IDOT TRAFFIC OFFICE AT 815/284-5469 AT LEAST 48 HOURS PRIOR TO WORK.


THE APPLICABLE PORTIONS OF ARTICLE 105.07 OF THE STANDARD SPECIFICATION SHALL APPLY EXCEPT FOR THE FOLLOWING: THE CONTRACTOR SHALL BE RESPONSIBLE TO LOCATE THE VERTICAL DEPTHS OF THE UNDERGROUND UTILITIES WHICH MAY INTERFERE WITH CONSTRUCTION OPERATIONS. THIS WORK WILL NOT BE MEASURED OR PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICE FOR THE ITEM OF CONSTRUCTION INVOLVED.

PER SB 699 (90 DAY UTILITY RELOCATION LAW), ONCE RIGHT-OF-WAY IS CLEAR TO AWARD THE PROJECT, A NOTICE WILL BE SENT TO THE UTILITY COMPANIES INSTRUCTING THEM TO HAVE THEIR FACILITIES RELOCATED WITHIN 90 DAYS. ESTIMATED DATE RELOCATION COMPLETE = AWARD DATE + 100 DAYS.

CADD DATA WILL BE AVAILABLE TO CONTRACTORS AND CONSULTANTS WORKING ON THIS PROJECT. THIS INFORMATION WILL BE PROVIDED UPON REQUEST AS MICROSTATION CADD FILES AND GEOPAK COORDINATE GEOMETRY FILES ONLY. IF DATA IS REQUIRED IN OTHER FORMATS IT WILL BE YOUR RESPONSIBILITY TO MAKE THESE CONVERSIONS. IF ANY DISCREPANCY OR INCONSISTENCY ARISES BETWEEN THE ELECTRONIC DATA AND THE INFORMATION ON THE HARD COPY, THE INFORMATION ON THE HARD COPY SHOULD BE USED. CONTACT THE DISTRICT'S PROJECT ENGINEER TO REQUEST THESE FILES.

COMMITMENTS

1. TWO EXISTING FIELD ENTRANCES LOCATED APPROXIMATELY 4430 FEET AND 4950 FEET SOUTHEAST OF THE EXISTING BRIDGE PROJECT SITE ON THE NORTH SIDE OF THE ROADWAY, ARE TO BE REMOVED PER HIGHWAY PERMIT NO. A2-09-021, DATED APRIL 9, 2009. CULVERT REMOVAL, GRADING AND SEEDING FOR THE REMOVAL OF THESE TWO ENTRANCES ARE TO BE INCLUDED IN THE PROJECT WORK ACTIVITIES.
2. ANY DISTURBED AREA BETWEEN THE BOTTOM OF THE ROADWAY DITCH AND THE RAILROAD SHALL BE SEEDED WITH CLASS 4 AND CLASS 5 SEEDING MIX (AS SPECIFIED IN THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, JAN. 1, 2012). THIS IS TO MITIGATE THE REMNANT RAILROAD PRAIRIE WHICH WILL BE IMPACTED IN THIS AREA.
3. MITIGATION TREES SHALL NOT BE PLANTED IN THE AREA WHICH IS SEEDED ACCORDING TO COMMITMENT #1.

FILE NAME =	USER NAME = #USER#	DESIGNED - RAC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	 <small>Zroka Engineering, P.C. 4216 North Hermitage Chicago, IL 60613</small>	GENERAL NOTES AND COMMITMENTS	F.A.P. RTE. 646	SECTION 5 BR-3	COUNTY CARROLL	TOTAL SHEETS 84	SHEET NO. 4
#FILE#		DRAWN - SAW	REVISED -								
	PLOT SCALE = #SCALE#	CHECKED - DAZ	REVISED -								
	PLOT DATE = #DATE#	DATE - 10-11-13	REVISED -								
							SCALE:	SHEET 2 OF 2 SHEETS	STA.	TO STA.	
											ILLINOIS FED. AID PROJECT
											CONTRACT NO. 64084