


SUMMARY OF QUANTITIES					FUNDING: 80% FED : 20% STATE	
CODE NO.	ITEM	CONSTRUCTION CODE TYPE:	UNIT	TOTAL QUANTITY	0004	0011
					ROADWAY	SN 008-0014 (EX) SN 008-0051 (PR)
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)		UNIT	78	78	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)		UNIT	110	110	
20200100	EARTH EXCAVATION		CU YD	1465	1465	
20400800	FURNISHED EXCAVATION		CU YD	7330	7330	
* 25000210	SEEDING, CLASS 2A		ACRE	1.5	1.5	
* 25000310	SEEDING, CLASS 4		ACRE	0.5	0.5	
NP 25000750	MOWING		ACRE	1.25	1.25	
* 25100125	MULCH, METHOD 3		ACRE	0.5	0.5	
* 25100630	EROSION CONTROL BLANKET		SO YD	3284	3284	
* 25100900	TURF REINFORCEMENT MAT		SO YD	342	342	
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	336	336	
28000305	TEMPORARY DITCH CHECKS		FOOT	500	500	
28000400	PERIMETER EROSION BARRIER		FOOT	1361	1361	
28000500	INLET AND PIPE PROTECTION		EACH	2	2	

NP = Non-participating (100% State)  
\* SPECIALTY ITEMS

FILE NAME =	USER NAME = #USER#	DESIGNED - RAC	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	 Zroka Engineering, P.C. 4216 North Hermitage Chicago, IL 60613	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	PLOT SCALE = #SCALE#	DRAWN - SAW	REVISED -			646	5 BR-3	CARROLL	84	5		
	PLOT DATE = #DATE#	CHECKED - DAZ	REVISED -			CONTRACT NO. 64084						
		DATE - 10-11-13	REVISED -			ILLINOIS FED. AID PROJECT						