



PLAN FOR TOP OF SLAB ELEVATIONS

SOUTH EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
E. End W. Appr. Pvmt.	248+15.75	-16.00	711.79
A2	248+25.75	-16.00	711.84
B2	248+35.75	-16.00	711.90
W. End W. Appr. Pvmt.	248+45.75	-16.00	711.95

SOUTH EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
E. End W. Appr. Pvmt.	248+15.75	-12.00	711.88
A2	248+25.75	-12.00	711.93
B2	248+35.75	-12.00	711.98
W. End W. Appr. Pvmt.	248+45.75	-12.00	712.03

Q & PGL IL 40

Location	Station	Offset	Theoretical Grade Elevations
E. End W. Appr. Pvmt.	248+15.75	0.00	712.06
A2	248+25.75	0.00	712.11
B2	248+35.75	0.00	712.17
W. End W. Appr. Pvmt.	248+45.75	0.00	712.22

NORTH EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
E. End W. Appr. Pvmt.	248+15.75	12.00	711.88
A2	248+25.75	12.00	711.93
B2	248+35.75	12.00	711.98
W. End W. Appr. Pvmt.	248+45.75	12.00	712.03

NORTH EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
E. End W. Appr. Pvmt.	248+15.75	16.00	711.79
A2	248+25.75	16.00	711.84
B2	248+35.75	16.00	711.90
W. End W. Appr. Pvmt.	248+45.75	16.00	711.95

FILE NAME = ...E4DB4-SN0080051-006-WAppr-TSE.dgn



Zroka Engineering, P.C.
4216 North Hermitage
Chicago, IL 60613

USER NAME = SAW	DESIGNED - PMM	REVISED -
	CHECKED - DAZ	REVISED -
PLOT SCALE = 0:2.0000 't' / in.	DRAWN - SAW	REVISED -
PLOT DATE = 8/1/2013	CHECKED - PMM	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WEST APPROACH TOP OF SLAB ELEVATIONS
S.N. 008-0051

SHEET NO. 6 OF 19 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	5BR-3	CARROLL	84	29
CONTRACT NO. 64DB4				
ILLINOIS FED. AID PROJECT				