

PATCHING SCHEDULE

| LOCATION | REMARKS | LENGTH OF PATCH | | 44201019 | | 44201023 | | 44201025 | | 44201299 | 44213100 | 44213200 | 44213204 |
|---------------------------------|---------|-----------------|---------------|--------------------------|------------------|--------------------------|------------------|--------------------------|------------------|----------------------|--------------------|---------------------|---------------|
| | | | | CL B PATCH T2 14 INCH | | CL B PATCH T3 14 INCH | | CL B PATCH T4 14 INCH | | DOWEL BARS 1 1/2" | PAVEMENT FABRIC | SAW CUTS (3W+2L) | TIE BARS 3/4" |
| | | LT LANE FT | RT LANE FT | LT LANE SQ YD | RT LANE SQ YD | LT LANE SQ YD | RT LANE SQ YD | LT LANE SQ YD | RT LANE SQ YD | EA | SQ YD | FT | EA |
| EASTBOUND | | | | | | | | | | | | | |
| 610+00 - 610+10 | | 12 | 12 | | | 16 | 16 | | | 40 | 32 | 60 | |
| 612+41 - 612+47 | | | 6 | | 8 | | | | | 20 | | 48 | |
| 613+37 - 613+45 | | | 8 | | 11 | | | | | 20 | | 52 | |
| 623+24 - 623+32 | | | 8 | | 11 | | | | | 20 | | 52 | |
| 633+17 - 633+27 | | | 10 | | 13 | | | | | 20 | | 56 | |
| 647+11 - 647+23 | | | 12 | | | | 16 | | | 20 | 16 | 60 | |
| 659+99 - 660+07 | | | 8 | | 11 | | | | | 20 | | 52 | |
| 671+89 - 671+97 | | | 8 | | 11 | | | | | 20 | | 52 | |
| 682+34 - 682+42 | | | 8 | | 11 | | | | | 20 | | 52 | |
| 694+32 - 694+38 | | 6 | | 8 | | | | | | 20 | | 48 | |
| 700+00 - 700+40 | | 40 | 40 | | | | | 53 | 53 | 40 | 107 | 116 | 20 |
| 711+63 - 711+69 | | 6 | | 8 | | | | | | 20 | | 48 | |
| 712+83 - 712+89 | | | 6 | | 8 | | | | | 20 | | 48 | |
| 717+93 - 717+99 | | | 6 | | 8 | | | | | 20 | | 48 | |
| 718+63 - 718+69 | | | 6 | | 8 | | | | | 20 | | 48 | |
| 719+44 - 719+50 | | 6 | | 8 | | | | | | 20 | | 48 | |
| 725+22 - 725+28 | | 6 | | 8 | | | | | | 20 | | 48 | |
| 725+12 - 725+27 | | 6 | 15 | 8 | | | 20 | | | 40 | 20 | 66 | |
| 725+32 - 725+42 | | | 10 | | 13 | | | | | 20 | | 56 | |
| 726+93 - 726+99 | | | 6 | | 8 | | | | | 20 | | 48 | |
| 736+38 - 736+53 | | 15 | 10 | | 13 | 20 | | | | 40 | 20 | 66 | |
| 737+32 - 737+38 | | 6 | | 8 | | | | | | 20 | | 48 | |
| 738+47 - 738+55 | | 8 | | 11 | | | | | | 20 | | 52 | |
| 767+93 - 768+01 | | | 8 | | 11 | | | | | 20 | | 52 | |
| 777+30 - 777+38 | | | 8 | | 11 | | | | | 20 | | 52 | |
| 780+23 - 780+29 | | 6 | 6 | 8 | 8 | | | | | 40 | | 48 | |
| 787+22 - 787+28 | | 6 | | 8 | | | | | | 20 | | 48 | |
| 792+42 - 792+50 | | | 8 | | | | | | | 20 | | 52 | |
| 793+41 - 793+49 | | | 8 | | | | | | | 20 | | 52 | |
| 800+00 - 800+36 | | 36 | 36 | | | | | 48 | 48 | 40 | 96 | 108 | 18 |
| 847+37 - 847+49 | | | 12 | | | | 16 | | | 20 | 16 | 60 | |
| 876+17 - 876+23 | | 6 | | 8 | | | | | | 20 | | 48 | |
| 890+96 - 891+11 | | 15 | 15 | | | 20 | 20 | | | 40 | 40 | 66 | |
| 900+00 - 900+10 | | 10 | 10 | 13 | 13 | | | | | 40 | | 56 | |
| 903+52 - 903+60 | | | 8 | | 11 | | | | | 20 | | 52 | |
| 904+98 - 905+04 | | 6 | 6 | 8 | 8 | | | | | 40 | | 48 | |
| 992+33 - 992+33 | | | 6 | | 8 | | | | | 20 | | 48 | |
| 1000+00 - 1000+12 | | 12 | 12 | | | 16 | 16 | | | 40 | 32 | 60 | |
| 1009+69 - 1009+69 | | | 6 | | 8 | | | | | 20 | | 48 | |
| EASTBOUND PATCHING TOTAL | | | | 315 | | 176 | | 203 | | 980 | 379 | 2170 | 38 |
| PATCHING GRAND TOTAL | | | | 1,035 | | 264 | | 432 | | 2,840 | 696 | 6,424 | 89 |

| | | | |
|--|--|-------------|------------|
| FILE NAME = | USER NAME = grantm | DESIGNED -- | REVISED -- |
| D:\work\p\dod\grantm\40340\01\020813-10\patching.dgn | D:\work\p\dod\grantm\40340\01\020813-10\patching.dgn | DRAWN -- | REVISED -- |
| Default | PLOT SCALE = 100.0000 / in. | CHECKED -- | REVISED -- |
| | PLOT DATE = Mon Sep 15 09:44:05 2014 | DATE -- | REVISED -- |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PATCHING SCHEDULE

SCALE: SHEET OF SHEETS STA. TO STA.



| F.A.T. RTE: | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|---------------|--------|-----------------|--------------|
| 80 | 137-2.31 RS-3 | HENRY | 90 | 20 |
| CONTRACT NO. 64663 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |