

HOT-MIX ASPHALT SCHEDULE

LOCATION	REMARKS	LENGTH	PROPOSED SURFACE		40600990	40600845	40603153	X4060115
			WIDTH	AREA	TEMPORARY RAMP	P LEV BIND MM N90	P HMA SC SMA N80	P BIT MATLS PR CT
			FT	FT	SQ YD	SQ YD	TON	TON
EASTBOUND MAINLINE								
600+82 - 601+22	MILLING 4"	40	24	107	28	12	12	72
601+22 - 603+22	TAPER	200	24	533		60	60	360
603+22 - 724+06		12084	24	32224		3609	3609	21751
724+06 - 726+06	TAPER	200	24	533		60	60	360
726+06 - 726+46	MILLING 4"	40	24	107	28	12	12	72
726+46 - 724+96	(037-0107) BRIDGE OMISSION							
724+96 - 725+36	MILLING 4"	40	24	107	28	12	12	72
725+36 - 727+36	TAPER	200	24	533		60	60	360
727+36 - 784+67		5731	24	15282		1712	1712	10315
784+67 - 788+54	TAPER	388	24	1033		116	116	698
788+54 - 789+64	(037-0109) MILLING 4"	110	24	293		33	33	198
789+64 - 793+52	TAPER	388	24	1033		116	116	698
793+52 - 836+54		4302	24	11473		1285	1285	7744
836+54 - 841+42	TAPER	488	24	1300		146	146	878
841+42 - 842+52	(037-0110) MILLING 6"	110	24	293		33	33	198
842+52 - 847+39	TAPER	488	24	1300		146	146	878
847+39 - 971+47		12408	24	33087		3706	3706	22334
971+47 - 975+34	TAPER	388	24	1033		116	116	698
975+34 - 976+44	(037-0111) MILLING 4"	110	24	293		33	33	198
976+44 - 980+32	TAPER	388	24	1033		116	116	698
980+32 - 1014+00		3368	24	8982		1006	1006	6063
1014+00 - 1016+00	TAPER	200	24	533		60	60	360
1016+00 - 1020+30	MILLING 4"	430	24	1147	28	128	128	774
EASTBOUND TOTAL					113	12573	12573	75777