

# HOT-MIX ASPHALT SCHEDULE

LOCATION	REMARKS	LENGTH	PROPOSED SURFACE		40600990	40600845	40603153	X4060115
			WIDTH	AREA	TEMPORARY RAMP	P LEV BIND MM N90	P HMA SC SMA N80	P BIT MATLS PR CT
			FT	SQ YD	SQ YD	TON	TON	(2 APPL.) POUND
<b>WESTBOUND MAINLINE</b>								
1020+30 - 1016+00	MILLING 4"	430	24	1147	28	128	128	774
1016+00 - 1014+00	TAPER	200	24	533		60	60	360
1014+00 - 980+82		3318	24	8849		991	991	5973
980+82 - 976+44	TAPER	438	24	1167		131	131	788
976+44 - 975+34	(037-0111) MILLING 5"	110	24	293		33	33	198
975+34 - 970+97	TAPER	438	24	1167		131	131	788
970+97 - 847+14		12383	24	33021		3698	3698	22289
847+14 - 842+52	TAPER	463	24	1233		138	138	833
842+52 - 841+42	(037-0110) MILLING 5.5"	110	24	293		33	33	198
841+42 - 836+79	TAPER	463	24	1233		138	138	833
836+79 - 794+52		4227	24	11273		1263	1263	7609
794+52 - 789+64	TAPER	488	24	1300		146	146	878
789+64 - 788+54	(037-0109) MILLING 6"	110	24	293		33	33	198
788+54 - 783+67	TAPER	488	24	1300		146	146	878
783+67 - 727+36		5631	24	15015		1682	1682	10135
727+36 - 725+36	TAPER	200	24	533		60	60	360
725+36 - 724+96	MILLING 4"	40	24	107	28	12	12	72
724+96 - 723+46	(037-0108) BRIDGE OMISSION							
723+46 - 723+06	MILLING 4"	40	24	107	28	12	12	72
723+06 - 721+06	TAPER	200	24	533		60	60	360
721+06 - 614+24		10682	24	28486		3190	3190	19228
614+24 - 612+24	TAPER	200	24	533		60	60	360
612+24 - 600+82	MILLING 4"	1142	24	3044	28	341	341	2055
<b>WESTBOUND TOTAL</b>					<b>113</b>	<b>12484</b>	<b>12484</b>	<b>75237</b>
<b>MAINLINE TOTAL</b>					<b>230</b>	<b>25,057</b>	<b>25,057</b>	<b>151,013</b>