

GUARDRAIL SCHEDULE

LOCATION	REMARKS	48102100	50901705	63000001	63000003	63100045	63100089	63100101	63100167	63200310	63301210	63301215	63301990	63302000	63302400	63302700	63500105	78200410	78201000	X2800400	X6300130
		AGG WEDGE SHLD TYPE B	TUB THRBM RETRO RL BR	SPBGR TY A 6FT POSTS	SPBGR TY A 9FT POSTS	TRAF BAR TERM T2	TRAF BAR TERM T6B	TRAF BAR TERM T9	TR BAR TRM T1 SPL TAN	GUARDRAIL REMOVAL	REM RE-E SPBGR TY A	REM RE-E SPBGR TY B	REM RE-E T B TERM T1	REM RE-E T B TERM T2	REM RE-E T B TERM T5	REM RE-E T B TERM T6	DELINEATORS	GUARDRAIL MKR TYPE A	TERMINAL MARKER - DA	PERIMETER EROS BAR SP	SPBGR TY A SPL
		TON	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	FOOT	FOOT
EASTBOUND																					
600+82 - 601+34	OSCO RD. - OUTSIDE SHOULDER (SN 037-0033)										25.0				1	1		4			
600+82 - 601+34	OSCO RD. - INSIDE SHOULDER (SN 037-0033)										25.0				1	1		4			
671+16 - 674+79	7271 FT E. OF OSCO RD. (SN 037-0033)										300.0		1	1			1	5	1		
685+79 - 694+35	8980 FT E. OF OSCO RD. (SN 037-0033)			37.5							737.5		1	1			1	10	1		
721+20 - 725+58	MINERAL CREEK BRIDGE - OUTSIDE SHOULDER (SN 037-0107)		150.0	175.0		1		2	1	438							1	6	1		
721+81 - 725+43	MINERAL CREEK BRIDGE - INSIDE SHOULDER (SN 037-0107)		150.0	275.0		1		2	1	363							1	7	1		
786+47 - 789+15	E. 950TH ST. (SN 037-0109)							1		63	162.5		1				1	4	1		
839+34 - 842+03	E. 1050TH ST. (SN 037-0110)							1		63	162.5		1				1	4	1		
955+25 - 958+53	11492 FT. E. OF E. 1050TH ST. (SN 037-0110)										262.5		1	1			1	4	1		
972+77 - 975+96	E. 1300TH ST. (SN 037-0111)							1		63	212.5		1				1	4	1		
EASTBOUND TOTAL		0	300.0	487.5	0.0	2	3	4	2	988	1887.5		6	5	2	0	8	52	8	0.0	0.0
WESTBOUND																					
979+14 - 975+83	E. 1300TH ST. (SN 037-0111)							1		63	225.0		1				1	4	1		
958+31 - 956+06	1871 FT W. OF E. 1300TH ST. (SN 037-0111)			162.5		1			1	300							1	4	1		
844+59 - 841+90	E. 1050TH ST. (SN 037-0110)							1		63	162.5		1				1	4	1		
831+67 - 824+26	1400 FT W. OF E. 1050TH ST. (SN 037-0110)	60			687.5	1			1	700							1	10	1	375.0	287.5
813+94 - 810+19	2990 FT W. OF E. 1050TH ST. (SN 037-0110)									50	312.5		1	1			1	5	1		
791+84 - 789+03	E. 950TH ST. (SN 037-0109)							1		63	175.0		1				1	4	1		
743+83 - 736+71	4882 FT W. OF E. 950TH ST. (SN 037-0109)									38	650.0		1	1			1	5	1		
727+25 - 722+75	MINERAL CREEK BRIDGE - OUTSIDE SHOULDER (SN 037-0108)		150.0	187.5		1		2	1	450							1	6	1		
726+50 - 722+92	MINERAL CREEK BRIDGE - INSIDE SHOULDER (SN 037-0108)		150.0	275.0		1		2	1	363							1	7	1		
698+43 - 688+55	6439 FT W. OF E. 950TH ST. (SN 037-0109)	150									925.0		1	1			1	12	1	925.0	700.0
678+25 - 671+71	11411 FT W. OF E. 950TH ST. - OUTSIDE SHOULDER (SN 037-0109)			587.5		1			1	650							1	4	1		
673+88 - 671+63	11634 FT W. OF E. 950TH ST. - INSIDE SHOULDER (SN 037-0109)										162.5		1	1			1	4	1		
638+07 - 636+15	15198 FT W. OF E. 950TH ST. - INSIDE SHOULDER (SN 037-0109)										87.5	37.5	1	1			1	4	1		
637+68 - 636+14	15218 FT W. OF E. 950TH ST. - OUTSIDE SHOULDER (SN 037-0109)										50.0	37.5	1	1			1	4	1		
604+76 - 600+82	OSCO RD. - INSIDE SHOULDER (SN 037-0034)									75	300.0		1			1	1	5	1		
WESTBOUND TOTAL		210	300.0	1212.5	687.5	5	3	4	5	2813	3050.0	75.0	10	6	0	1	15	82	15	1300.0	987.5
TOTAL		210	600	1,700.0	687.5	7	6	8	7	3,801	4,937.5	75.0	16	11	2	1	23	134	23	1,300.0	987.5