

# GENERAL NOTES

Delineators shall be installed as shown in Standard 635001, except that the post shall be rotated 180° and only metal-backed delineators shall be permitted. Delineators shall be placed at the ends of approach guardrail terminal sections, and at each headwall or end section of AR Culverts. This work will be paid for at the contract unit price each for DELINEATORS.

The Contractor shall be responsible for collecting and maintaining an electronic log of all stakeout survey that is performed on the job, either by him/her or any sub-contractor performing the stakeout. Upon request, all logs shall be submitted to the Department. No additional compensation will be allowed for this work, but shall be considered included in the cost for CONSTRUCTION LAYOUT.

Pavement Marking shall be done according to Standard 780001, except as follows:

1. All words, such as ONLY, shall be 8 feet high.
2. All non-freeway arrows shall be the large size.
3. The distance between yellow no-passing lines shall be 8 inches, not 7 inches, as shown in the detail of Typical Lane and Edge Lines.
4. Centerline Skip Dash Pavement Marking on multi-lane divided, multi-lane undivided, and one-way roadway shall be according to District Standard 41.1.

Tree planting layout shall be performed by the District Roadside Management Specialist. Mulch shall be placed 4" thick and to the diameter around the tree as shown on District Standard 92.1. The mulch shall be hardwood wood chips placed on weed barrier fabric. This work shall be included in the cost of the tree.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Commonwealth Edison (815) 490-2869	Farmers Mutual Electric Co. (309) 944-4669
Geneseo Telephone Company (309) 944-8012	AT&T (309) 686-3317
Ameren IP (309) 345-5173	Corn Belt Energy Corp. (815) 875-4480
NICOR Gas (630) 983-8676	Mediacom (309) 743-4750
MCI World Com (972) 729-6016	City of Geneseo (309) 944-8424
Natural Gas Pipeline (309) 944-4676	

IDOT is not a member of JULIE. If you are near any overhead lighting, intersection lighting or traffic signals, contact the IDOT Traffic Office at 815/284-5469 at least 48 hours prior to work.

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

Excess trees that cannot be planted along the Interstate 80 project limits shall be planted at alternative locations as determined by the District Roadside Management Specialist.

During grinding operations, concrete patches will be encountered. The grinding of the concrete shall not be paid for separately, but be included in the cost of HMA SURFACE REMOVAL of the thickness specified.

## Commitments

In the tree removal area at Station 1208 + 30, there is a wetland located at the bottom of the foreslope beyond the trees. This wetland will not be impacted by storing equipment and materials, driving vehicles and equipment through the wetland, or placing fill in the wetland.

FILENAME = G4954.GN.DOCX	USERNAME =	DESIGNED = Engineering Systems	REVISED =	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES</b>	ROUTE	SECTION	COUNTY	TWA SHEETS	SHEET NO.	
	PLOT SCALE =	CHECKED =	REVISED =			80 (1:50)	(37-4.5.6)RS-2	Henry	80	4	
	PLOT DATE = 8/21/2014 2:55 PM	DATE = 7/21/2014 1:35 PM	REVISED =			CONTRACT NO. 54G64			ILLINOIS		FED. AID PROJECT
						SCALE:	SHEET NO.	OF	SHEETS	STA	TO STA.