

SUMMARY OF QUANTITIES

CONSTR. CODE
90% FEDERAL
10% STATE
ROADWAY
0005
RURAL

PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
40600990	TEMPORARY RAMP	SQ YD	1,173	90% FEDERAL 10% STATE ROADWAY 0005 RURAL
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	55,210	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	36,403	
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,137	
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	451,515	
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	44,090	
44201043	CLASS B PATCHES, TYPE II, 16 INCH	SQ YD	159	
44201047	CLASS B PATCHES, TYPE III, 16 INCH	SQ YD	243	
44201048	CLASS B PATCHES, TYPE IV, 16 INCH	SQ YD	2,223	
44201299	DOWEL BARS 1 1/2"	EACH	920	
44213100	PAVEMENT FABRIC	SQ YD	2,466	
44213200	SAW CUTS	FOOT	5,506	
44213204	TIE BARS 3/4"	EACH	817	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	21,773	

*SPECIALTY ITEMS

• (37-4.5,6) RS-2

FILE NAME *	USER NAME * grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 80	SECTION *	COUNTY HENRY	TOTAL SHEETS 80	SHEET NO. 6
Default	11-sh1-schedule.dgn	DRAWN -	REVISIED -							
	PLOT SCALE * 1/8" = 1' / in.	CHECKED -	REVISIED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
	PLOT DATE * Fri Aug 22 20:38:00 2014	DATE -	REVISIED -							
										CONTRACT NO. 64664
										ILLINOIS FED. AID PROJECT