

SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	STATION	(DIR)	REMARKS
8	1325+05	EB	ON A FORESLOPE < 1:3 W/IN CZ
6	1325+40	EB	ON A FORESLOPE < 1:3 W/IN CZ
15	1510+21	WB	
10	1516+11	WB	
8	1522+10	WB	
10	1524+98	WB	
10	1524+98	WB	
9	1556+49	WB	
6	1592+13	WB	
6	1592+94	WB	
10	1630+04	WB	
TOTAL	98		

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	STATION	(DIR)	REMARKS
25	1630+45	WB	
25	1631+89	WB	
32	1633+66	WB	
20	1639+17	WB	
TOTAL	102		

20100500 TREE REMOVAL, ACRES

ACRE	STATION	STATION	(DIR)	REMARKS
0.12	1207+38	TO 1209+23	EB	15' BEYOND THE TOE OF SLOPE
0.02	1636+42	TO 1636+70	WB	
TOTAL	0.14			

25000210 SEEDING, CLASS 2A

ACRE	STATION	STATION	(DIR)	REMARKS
0.16	1207+38	TO 1209+23	EB	INCLUDES APROX. 50' ACCESS PATH TO SITE
0.07	1325+05		EB	ON A FORESLOPE < 1:3 W/IN CZ INCLUDES APPROX 25' PATH
0.07	1325+40		EB	ON A FORESLOPE < 1:3 W/IN CZ INCLUDES APPROX 25' PATH
0.07	1510+21		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.07	1516+11		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.07	1522+10		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.07	1524+98		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.07	1524+98		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.07	1556+49		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.07	1592+13		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.07	1592+94		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.06	1630+04		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.07	1630+45		WB	25 UNIT SIZED TREE
0.07	1631+89		WB	25 UNIT SIZED TREE
0.07	1633+66		WB	32 UNIT SIZED TREE
0.07	1639+17		WB	20 UNIT SIZED TREE
0.04	1636+42	TO 1636+70	WB	INCLUDES APROX. 25' ACCESS PATH TO SITE
TOTAL	1.25			

25100125 MULCH, METHOD 3

ACRE	STATION	STATION	(DIR)	REMARKS
0.12	1207+38	TO 1209+23	EB	TREE REMOVAL SITE ONLY
0.06	1325+05		EB	ON A FORESLOPE < 1:3 W/IN CZ INCLUDES APPROX 25' PATH
0.06	1325+40		EB	ON A FORESLOPE < 1:3 W/IN CZ INCLUDES APPROX 25' PATH
0.06	1510+21		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.06	1516+11		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.06	1522+10		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.06	1524+98		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.06	1524+98		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.06	1556+49		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.06	1592+13		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.06	1592+94		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.06	1630+04		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
0.06	1630+45		WB	25 UNIT SIZED TREE
0.06	1631+89		WB	25 UNIT SIZED TREE
0.06	1633+66		WB	32 UNIT SIZED TREE
0.06	1639+17		WB	20 UNIT SIZED TREE
0.02	1636+42	TO 1636+70	WB	TREE REMOVAL SITE ONLY
TOTAL	1.03			

25100630 EROSION CONTROL BLANKET

SQ YD	STATION	STATION	(DIR)	REMARKS
166.7	1207+38	TO 1207+88	EB	APROX. 50' ACCESS PATH TO SITE ONLY
83.3	1325+05		EB	ON A FORESLOPE < 1:3 W/IN CZ INCLUDES APPROX 25' PATH
83.3	1325+40		EB	ON A FORESLOPE < 1:3 W/IN CZ INCLUDES APPROX 25' PATH
83.3	1510+21		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
83.3	1516+11		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
83.3	1522+10		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
83.3	1524+98		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
83.3	1524+98		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
83.3	1556+49		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
83.3	1592+13		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
83.3	1592+94		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
83.3	1630+04		WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
83.3	1630+45		WB	25 UNIT SIZED TREE
83.3	1631+89		WB	25 UNIT SIZED TREE
83.3	1633+66		WB	32 UNIT SIZED TREE
83.3	1639+17		WB	20 UNIT SIZED TREE
83.3	1636+45	TO 1636+70	WB	INCLUDES APROX. 25' ACCESS PATH TO SITE
TOTAL	1500			

• (37-4,5,6) RS-2

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwork\pwork\grantpm\d0310501\200711-sh-t-schedule.dgn		DRAWN -	REVISED -		80	*	HENRY	80	21			
Default	PLOT SCALE = 100.000' / in.	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.			CONTRACT NO. 64664				
	PLOT DATE = Thu Aug 21 13:07:15 2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							