

# HOT-MIX ASPHALT SCHEDULE

	X4060115	44000156	44000165	X4401198	40600990	40600845	40603153			
EASTBOUND	BEGIN	END	LENGTH (ft)	POLYMERIZED BIT. MATERIALS (PRIME COAT) (lbs.) (2 APPL.)	HMA SURFACE REMOVAL 1 3/4" (sq yd)	HMA SURFACE REMOVAL 4" (sq yd)	HMA SURFACE REMOVAL (VARIABLE DEPTH) (sq yd)	TEMPORARY RAMPS (sq yd)	2" POLYMERIZED LEVELING BINDER (MM), N90 (ton)	2" POLYMERIZED HMA SURFACE COURSE, SMA, N80 (ton)
<b>BEGIN JOB</b>	1020+30	1021+35	105	189		280		25	21	29
	1021+35	1022+48	113	203			301		34	34
	1022+48	1028+48	600	1080	1600				179	179
<b>Transition to 3 lanes</b>	1028+48	1031+18	270	608	900				101	101
<b>3 Lanes</b>	1031+18	1041+08	990	2673	3960				444	444
	1041+08	1042+61	153	413	612			25	21	64
<b>Bridge Omission</b>	1042+61	1045+80	319							
	1045+80	1047+33	153	275	408			25	21	43
	1047+33	1050+61	328	590	875				98	98
	1050+61	1052+14	153	275	408			25	21	43
<b>Bridge Omission</b>	1052+14	1057+23	509							
	1057+23	1058+76	153	275	408			25	21	43
	1058+76	1067+24	848	1526	2261				253	253
<b>3 Lanes</b>	1067+24	1085+63	1839	4965	7356				824	824
<b>Transition to 2 lanes</b>	1085+63	1091+13	550	1238	1833				205	205
	1091+13	1099+36	823	1481	2195				246	246
	1099+36	1100+49	113	203			301		34	34
<b>(1101+01) 1500E/Conc Med</b>	1100+49	1115+40	1491	2684		3976			445	445
	1115+40	1116+53	113	203			301		34	34
	1116+53	1159+64	4311	7760	11496				1288	1288
	1159+64	1160+77	113	203			301		34	34
<b>1600E (1161+63)</b>	1160+77	1161+93	116	209		309			35	35
	1161+93	1163+06	113	203			301		34	34
	1163+06	1253+07	9001	16202	24003				2688	2688
	1253+07	1254+60	153	275	408			25	21	43
<b>Bridge Omission</b>	1254+60	1256+83	223							
	1256+83	1258+36	153	275	408			25	21	43
	1258+36	1315+73	5737	10327	15299				1713	1713
	1315+73	1317+26	153	275	408			25	21	43
<b>Bridge Omission</b>	1317+26	1318+51	125							
	1318+51	1320+04	153	275	408			25	21	43
	1320+04	1421+47	10143	18257	27048				3029	3029
	1421+47	1422+60	113	203			301		34	34
<b>(1423+29) 2100E/Conc Med</b>	1422+60	1434+45	1185	2133		3160			354	354
	1434+45	1435+58	113	203			301		34	34
	1435+58	1462+67	2709	4876	7224				809	809
	1462+67	1463+80	113	203			301		34	34
<b>Atkinson Rd (1464+48)</b>	1463+80	1465+07	127	229		339			38	38
	1465+07	1466+20	113	203			301		34	34
	1466+20	1535+05	6885	12393	18360				2056	2056
	1535+05	1536+18	113	203			301		34	34
<b>Concrete Median (1541+00)</b>	1536+18	1545+82	964	1735		2571			288	288
	1545+82	1546+95	113	203			301		34	34
	1546+95	1556+46	951	1712	2536				284	284
	1556+46	1557+59	113	203			301		34	34
<b>2350E (1558+25)</b>	1557+59	1558+94	135	243		360			40	40
	1558+94	1560+07	113	203			301		34	34
	1560+07	1608+32	4825	8685	12867				1441	1441
	1608+32	1609+85	153	275	408			25	21	43
<b>Bridge Omission</b>	1609+85	1613+65	380							
	1613+65	1615+18	153	275	408			25	21	43
	1615+18	1647+05	3187	5737	8499				952	952
	1647+05	1648+18	113	203			301		34	34
<b>2500E (1649+11)</b>	1648+18	1649+40	122	220		325			36	36
	1649+40	1650+53	113	203			301		34	34
	1650+53	1751+80	10127	18229	27005				3025	3025
	1751+80	1753+33	153	275	408			25	21	43
<b>Bridge Omission</b>	1753+33	1755+67	234							
	1755+67	1757+00	133	239		355		25	40	40
<b>Concrete Median (1761+78)</b>	1757+00	1766+56	956	1721		2549			286	286
	1766+56	1767+69	113	203			301		34	34
	1767+69	1791+47	2378	4280	6341				710	710
	1791+47	1792+60	113	203			301		34	34
<b>IL 78 (1793+31)</b>	1792+60	1793+88	128	230		341			38	38
	1793+88	1795+01	113	203			301		34	34
	1795+01	1873+34	7833	14099	20888				2339	2339
	1873+34	1874+47	113	203			301		34	34
<b>2900E (1875+23)</b>	1874+47	1875+68	121	218		323			36	36
	1875+68	1876+81	113	203			301		34	34
	1876+81	1928+43	5162	9292	13765				1542	1542
<b>END JOB</b>	1928+43	1929+96	153	275	408			25	21	43
	<b>EB TOTAL:</b>			163570	221411	14888	6027	345	26814	27103
							Z0034105	MATERIAL TRANSFER DEVICE:		53917

• (37-4,5,6) RS-2

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>HOT-MIX ASPHALT SCHEDULE</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	ca:\pwork\pwork\dot\grantpm\d0310501\200711-shit-schedule.dgn	DRAWN -	REVISED -			80	*	HENRY	80	26
	PLOT SCALE = 100.000' / in.	CHECKED -	REVISED -					CONTRACT NO. 64G64		
	PLOT DATE = Thu Aug 21 13:08:30 2014	DATE -	REVISED -					ILLINOIS FED. AID PROJECT		
					SCALE:	SHEET	OF	SHEETS	STA.	TO STA.