

SHOULDER SCHEDULE

	40600982	44000165	X4401198	X4060110	X4060110	40603310	40603310	48203100	48101200			
EASTBOUND 4' SHOULDER	BEGIN	END	LENGTH (ft)	HMA SURFACE REMOVAL - BUTT JOINT (sq yd)	HMA SURFACE REMOVAL 4" (sq yd)	HMA SURFACE REMOVAL (VARIABLE DEPTH) (sq yd)	BITUMINOUS MATERIALS (PRIME COAT) (lbs.) (2 APPL.)	BITUMINOUS MATERIALS (PRIME COAT) (lbs.) (1 APPL)	2.25" HMA SURFACE COURSE, MIX C, N50 (ton)	2" HMA SURFACE COURSE, MIX C, N50 (ton)	2" HMA SHOULDERS (ton)	AGGREGATE SHOULDER, TYPE B (ton)
BEGIN/Median Omiss.	1020+30	1021+35	105									
	1021+35	1022+48	113			50	34		6			7
	1022+48	1041+08	1860					372	104			119
	1041+08	1042+61	153	68				31	9			10
Bridge Omission	1042+61	1045+80	319									
	1045+80	1047+33	153	68				31	9			10
	1047+33	1050+61	328					66	18			21
	1050+61	1052+14	153	68				31	9			10
Bridge Omission	1052+14	1057+23	509									
	1057+23	1058+76	153	68				31	9			10
	1058+76	1099+36	4060					812	227			259
	1099+36	1100+49	113			50	34		6		9	7
1500E	1100+49	1106+02	553		246		166			28	28	35
Median Omission	1106+02	1115+40	938									
	1115+40	1116+93	153	68				31	9		9	10
	1116+93	1159+64	4271					854	239			272
	1159+64	1160+77	113			50	34		6		9	7
1600E	1160+77	1161+93	116		52		35			6	6	7
	1161+93	1163+06	113			50	34		6		9	7
	1163+06	1253+07	9001					1800	504			574
	1253+07	1254+60	153	68				31	9			10
Bridge Omission	1254+60	1256+83	223									
	1256+83	1258+36	153	68				31	9			10
	1258+36	1315+73	5737					1147	321			366
	1315+73	1317+26	153	68				31	9			10
Bridge Omission	1317+26	1318+51	125									
	1318+51	1320+04	153	68				31	9			10
	1320+04	1421+47	10143					2029	568			647
	1421+47	1422+60	113			50	34		6		9	7
2100E	1422+60	1425+01	241		107		72			12	12	15
Median Omission	1425+01	1434+45	944									
	1434+45	1435+98	153	68				31	9		9	10
	1435+98	1462+67	2669					534	149			170
	1462+67	1463+80	113			50	34		6		9	7
CO HWY 5 (Atkinson)	1463+80	1465+07	127		56		38			6	6	8
	1465+07	1466+20	113			50	34		6		9	7
	1466+20	1535+05	6885					1377	386			439
	1535+05	1536+18	113	50				23	6		9	7
Median Omission	1536+18	1545+82	964									
	1545+82	1547+35	153	68				31	9		9	10
	1547+35	1556+46	911					182	51			58
	1556+46	1557+59	113			50	34		6		9	7
2350E	1557+59	1558+94	135		60		41			7	7	9
	1558+94	1560+07	113			50	34		6		9	7
	1560+07	1608+32	4825					965	270			308
	1608+32	1609+85	153	68				31	9			10
Bridge Omission	1609+85	1613+65	380									
	1613+65	1615+18	153	68				31	9			10
	1615+18	1647+05	3187					637	178			203
	1647+05	1648+18	113			50	34		6		9	7
2500E	1648+18	1649+40	122		54		37			6	6	8
	1649+40	1650+53	113			50	34		6		9	7
	1650+53	1751+80	10127					2025	567			646
	1751+80	1753+33	153	68				31	9			10
Bridge Omission	1753+33	1755+67	234									
	1755+67	1757+00	133		59		40		7	7	7	8
Median Omission	1757+00	1766+56	956									
	1766+56	1768+09	153	68				31	9		9	10
	1768+09	1791+47	2338					468	131			149
	1791+47	1792+60	113			50	34		6		9	7
IL 78	1792+60	1793+88	128		57		38			6	6	8
	1793+88	1795+01	113			50	34		6		9	7
	1795+01	1873+34	7833					1567	439			500
	1873+34	1874+47	113			50	34		6		9	7
2900E	1874+47	1875+68	121		54		36			6	6	8
	1875+68	1876+81	113			50	34		6		9	7
	1876+81	1928+43	5162					1032	289			329
END JOB	1928+43	1929+96	153	68				31	9			10
	EB TOTAL:			1138	745	753	1011	16406	4689	83	261	5438

• (37-4,5,6) RS-2

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SHOULDER SCHEDULE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	es:\pwork\pwork\dot\grantpm\0310501\020011-sh-t-schedule.dgn	DRAWN -	REVISED -			80	*	HENRY	80	28
	PLOT SCALE = 100.000' / in.	CHECKED -	REVISED -							CONTRACT NO. 64064
	PLOT DATE = Thu Aug 21 13:09:02 2014	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA. TO STA.
										ILLINOIS FED. AID PROJECT