

MAINLINE SCHEDULE

LOCATION			LENGTH	WIDTH	WIDTH W/PAVED SHLD.	AREA W/PAVED SHLD.	BIT MAT (PR CT)	MIX FOR CRACKS, JTS & FLGWYS	LEVEL BIND (HM) IL-9.5FG, N50	LEVEL BIND (MM) IL-9.5FG, N50	HMA SURF. CSE., MIX C N 50	MATERIAL TRANSFER DEVICE	HMA SURF REM 2-1/4"	TEMP RAMP	AGG WEDGE SHLD TYPE B
STA	TO	STA	FOOT	FOOT	FOOT	SQ YD	POUND	TON	TON	TON	TON	TON	SQ YD	SQ YD	TON
369+85	TO	373+60	375	24	26	1083	731	0.33	0.54	46	91	91	1083		10.7
373+60	TO	376+45	285	24	24	760	513	0.23	0.38	32	64	64	760		8.1
376+45	TO	381+03	458	24	24	1221	824	0.37	0.61	51	103	103	1221		13.0
381+03	TO	381+35	32	24	24	85	58	0.03	0.04	4	7	7	85		0.9
381+35	TO	384+07	272	24	26	786	530	0.24	0.39	33	66	66	786		7.7
384+07	TO	386+06	199	24	26	575	388	0.17	0.29	24	48	48	575		5.7
386+06	TO	394+43	837	24	27	2511	1695	0.75	1.26	105	211	211	2511		11.9
394+43	TO	397+27	284	24	27	852	575	0.26	0.43	36	72	72	852		4.0
397+27	TO	399+47	220	24	25	611	413	0.18	0.31	26	51	51	611		3.1
399+47	TO	401+25	178	24	25	494	334	0.15	0.25	21	42	42	494		2.5
LASALLE COUNTY TOTALS						81103	54744	24	41	3406	6813	6813	81103	60	662
401+25	TO	414+26	1301	24	25	3614	2439	1.08	1.81	152	304	304	3614		18.5
414+26	TO	414+58	32	24	27	96	65	0.03	0.05	4	8	8	96		0.5
414+58	TO	417+04	246	24	31	847	572	0.25	0.42	36	71	71	847		7.0
417+04	TO	417+81	77	24	31	265	179	0.08	0.13	11	22	22	265		2.2
417+81	TO	418+60	79	24	27	237	160	0.07	0.12	10	20	20	237		2.2
418+60	TO	422+90	430	24	27	1290	871	0.39	0.65	54	108	108	1290		12.2
422+90	TO	426+50	360	24	26	1040	702	0.31	0.52	44	87	87	1040		10.2
426+50	TO	429+70	320	24	24	853	576	0.26	0.43	36	72	72	853		9.1
429+70	TO	430+15	45	24	25	125	84	0.04	0.06	5	11	11	125		1.3
430+15	TO	433+25	310	24	25	861	581	0.26	0.43	36	72	72	861		8.8
433+25	TO	434+36.71 BK	112	24	28	348	235	0.10	0.17	15	29	29	348		3.2
434+36.89 AH		438+90	453	24	28	1410	952	0.42	0.70	59	118	118	1410		12.9
438+90	TO	439+82.20	92	24	27	277	187	0.08	0.14	12	23	23	277		2.6
439+82.20	TO	441+80	198	24	27	593	401	0.18	0.30	25	50	50	593		5.6
441+80	TO	448+50	670	24	27	2010	1357	0.60	1.01	84	169	169	2010		19.1
448+50	TO	456+72	822	24	27	2466	1665	0.74	1.23	104	207	207	2466		23.4
456+72	TO	459+86	314	24	27	942	636	0.28	0.47	40	79	79	942		
459+86	TO	460+92	106	24	24	283	191	0.08	0.14	12	24	24	283		
460+92	TO	463+05	213	24	25	592	399	0.18	0.30	25	50	50	592		
463+05	TO	467+87	482	24	27	1446	976	0.43	0.72	61	121	121	1446		
467+87	TO	469+99.61 BK	213	24	31	732	494	0.22	0.37	31	62	62	732	20	
470+00 AH	TO	470+67	SN 032-0085 OMISSION												
470+67	TO	471+69	102	24	31	351	237	0.11	0.18	15	30	30	351	20	2.9
471+69	TO	474+50	281	24	24	749	506	0.22	0.37	31	63	63	749		8.0
474+50	TO	478+69	419	24	24	1117	754	0.34	0.56	47	94	94	1117		11.9
478+69	TO	481+05	236	24	24	629	425	0.19	0.31	26	53	53	629		3.4
481+05	TO	484+93	388	24	27	1164	786	0.35	0.58	49	98	98	1164		5.5
484+93	TO	487+25	232	24	27	696	470	0.21	0.35	29	58	58	696		3.3
487+25	TO	490+86	361	24	27	1083	731	0.32	0.54	45	91	91	1083		5.1
490+86	TO	499+90	904	24	27	2712	1831	0.81	1.36	114	228	228	2712		25.7
499+90	TO	510+66.74 BK	1077	24	31	3709	2503	1.11	1.85	156	312	312	3709		30.7
510+66.76 AH	TO	511+20	54	24	31	187	126	0.06	0.09	8	16	16	187		1.5
511+20	TO	516+33	513	24	31	1767	1193	0.53	0.88	74	148	148	1767		7.3
516+33	TO	516+70	37	24	28	115	78	0.03	0.06	5	10	10	115		0.5
516+70	TO	520+70.88 BK	401	24	27	1203	812	0.36	0.60	51	101	101	1203		11.4
520+70.88 AH	TO	522+65	223	24	27	669	452	0.20	0.33	28	56	56	669		6.3
522+65	TO	546+36	2371	24	25	6586	4446	1.98	3.29	277	553	553	6586		67.5
546+36	TO	593+57.25 BK	4721	24	24	12590	8498	3.78	6.30	529	1058	1058	12590		134.4
593+57.25 AH	TO	47+50	949	24	24	2530	1708	0.76	1.27	106	213	213	2530	20	27.0
GRUNDY COUNTY TOTALS							39275	17	29	2444	4888	4888	58185	60	492
TOTALS							94019	42	70	5850	11700	11700	139287	120	1153