

PAVEMENT MARKING SCHEDULE														
LOCATION STA TO STA			LENGTH FOOT	POLYUREA TYPE 1 PAVEMENT MARKING				TEMPORARY PAVEMENT MARKING			SHORT-TERM PAVEMENT MARKING FOOT	WORK ZONE PVMT MARK REMOVAL SQ FT	RAISED REFL PVMT MARK REM EACH	RAISED REFL PVMT MARK EACH
				WHITE 4 INCH FOOT	YELLOW 4 INCH FOOT	YELLOW 6 INCH FOOT	WHITE 24 INCH FOOT	WHITE 4 INCH FOOT	YELLOW 4 INCH FOOT	YELLOW 6 INCH FOOT				
116+90	TO	134+44.61 BK	1755	3510	2990	118		7020	5980	235	527	176	22	22
134+44.13 AH	TO	170+01.59 BK	3557	7114	5320	385		14228	10640	769	1067	356	44	44
170+00 AH	TO	198+10 BK	2810	5620	2848	618		11240	5696	1236	843	281	35	35
198+05 AH	TO	215+05.57 BK	1701	3402	2402	250		6804	4803	500	510	170	21	21
215+00 AH	TO	401+25	18625	37250	20904	3274		74500	41808	6549	5588	1863	233	233
LASALLE COUNTY TOTALS				56896	34464	4644	0	113792	68928	9289	8534	2845	356	356
401+25	TO	434+36.71 BK	3312	6624	3095	718		13248	6189	1436	994	331		
434+36.89 AH	TO	469+99.61 BK	3563	7125	2545	891		14251	5089	1781	1069	356	45	45
470+00 AH	TO	510+66.74 BK	4067	8134	5682	613		16268	11365	1226	1220	407	67	67
510+65.76 AH	TO	520+70.88 BK	1005	2010	1794	54		4020	3589	108	302	101	26	26
520+42 AH	TO	593+57.25 BK	7315	14630	920	1829		29260	1840	3658	2195	732	91	91
56+98.82 AH	TO	47+50	949	1898	0	237		3796	0	475	285	95	12	12
E. 29th COUNTY RD. IL 170								28						
GRUNDY COUNTY TOTALS				40421	14036	4341	55	80843	28073	8682	6063	2021	240	240
TOTALS				97317	48500	8986	55	194635	97000	17971	14598	4866	596	596

RUMBLE STRIPS 8"			
LOCATION		LENGTH	SIDE
START	END	FT	
LASALLE CO			
145+94	150+50	456	LEFT
145+94	150+50	456	RIGHT
155+72	169+12	1340	RIGHT
192+47	199+50	703	RIGHT
201+00	209+70	870	RIGHT
210+00	210+90	90	RIGHT
211+22	213+28	206	RIGHT
221+34	227+12	578	LEFT
235+50	240+00	450	LEFT
227+93	240+00	1207	RIGHT
248+69	259+32	1063	LEFT
268+69	281+27	1258	LEFT
285+00	290+64	564	RIGHT
360+13	373+60	1347	RIGHT
381+35	397+27	1592	RIGHT
LASALLE CO TOTALS		12180	
GRUNDY CO			
414+26	426+50	1224	RIGHT
414+53	417+52	299	LEFT
433+25	459+86	2661	RIGHT
463+05	471+69	864	RIGHT
467+87	471+80	393	LEFT
481+05	516+40	3535	RIGHT
500+02	522+65	2263	LEFT
GRUNDY CO TOTALS		11239	
PROJECT TOTALS		23419	

PERMANENT SURVEY MARKERS						CONTRACT NO. 66B91
FOLDER 6-4		0.5 MI E OF CHICAGO ST. IN MARSEILLES TO 0.1 MI N OF MARSEILLES RD.			GRUNDY / LASALLE COUNTIES	
US ROUTE 6						
GPS POINT NUMBER OR INDEX NUMBER	DESCRIPTION	EXISTING MONUMENT TYPE	PROPOSED MONUMENT TYPE	MONUMENT RECORD TO BE RECORDED	RESPONSIBILITY	
6801	SW COR SEC 04-33-6E	SURVEY NAIL	TYPE 1	YES	1	

THIS NOTE TO BE INCLUDED IN PLANS:  
LISTED MONUMENT LOCATIONS HAVE BEEN RECORDED BY GPS. PRE CONSTRUCTION TIES BY THE R.E. ARE NOT REQUIRED.  
IF AN UNLISTED MONUMENT IS FOUND, IT MUST BE TIED BY THE R.E. AND BROUGHT TO THE ATTENTION OF THE PLATS AND PLANS MANAGER.  
AFTER RESURFACING, THE R.E. IS TO CONTACT THE PLATS AND PLANS MANAGER TO ESTABLISH LOCATIONS FOR PERMANENT SURVEY MARKER CORING.

**RESPONSIBILITY:**  
1) RESIDENT TO RE-ESTABLISH MONUMENT (PAY ITEM REQUIRED. PERMANENT SURVEY MARKER, TYPE 1)  
2) PLATS AND PLANS TO RE-ESTABLISH MONUMENT