

MAINLINE SCHEDULE																			
LOCATION IL 49	NOTES	LENGTH	PVMT WIDTH	SHLD WIDTH	HMA SURF. REM. VAR. DEPTH	BIT MAT PRIME COAT	LEVEL BINDER (MM, N50)	LEVEL BINDER (MM, N50)	HMA SURF CSE. MIX "C" N50	MIX FOR JOINTS, CRACKS, & FLANGWAYS	HMA BSE CSE VAR. DEPTH	HMA PVT FULL DEPTH 10 1/4"	SUBBASE GR MAT TY. A 12"	TEMP RAMP	HMA SHLD 8"	HMA SHLD	HMA PVT FULL DEPTH 10 1/4"	AGG SHLD TY. B	AGG SURF CSE. TY. B
STA. TO STA.		FOOT	FOOT	FOOT	SO YD	FOOT	TON	TON	TON	TON	TON	SO YD	SO YD	SO YD	SO YD	TON	TON	SO YD	TON
STA. 1222+00 TO STA. 1223+86.5	BEGIN PROJECT	187	24	9	545	335.7	20.9	0.25	42	0.15	22	37	67	20	33	69	126	4	
STA. 1223+86.5 TO STA. 1224+13.5	S.N. 038-2506	27	24	10	60	48.6	3	0.04	6	0.02		32	132		54				
STA. 1224+13.5 TO STA. 1226+30.0	END PROJECT	217	24	10	670	389.7	24.2	0.29	49	0.17	53	37	67	20	72	77	126	7	120
<b>TOTAL</b>					<b>1275</b>	<b>774</b>	<b>48</b>	<b>0.6</b>	<b>96</b>	<b>0.34</b>	<b>75</b>	<b>147</b>	<b>267</b>	<b>40</b>	<b>159</b>	<b>146</b>	<b>126</b>	<b>11</b>	<b>120</b>

PAVEMENT MARKING SCHEDULE								
LOCATION IL 49	NOTES	LENGTH	PAINT PVMT MK 4"	PAINT PVMT MK 6"	RAISED REF PVMT MARK REMOVAL	RAISED REFLECT PVMT MARK	SHORT TERM	WORK ZONE PVT MRK REMOVAL
STA. TO STA.		FOOT	FOOT	FOOT	EACH	EACH	FOOT	SO FT
STA. 1222+00 TO STA. 1223+72.5	BEGIN PROJECT	172.5	690	90	4	4	35	12
STA. 1223+72.5 TO STA. 1224+13.5	S.N. 038-2506	41	164	20	1	1	8	3
STA. 1224+13.5 TO STA. 1226+30.0	END PROJECT	216.5	866	110	5	5	43	14
<b>TOTAL</b>			<b>1720</b>	<b>220</b>	<b>10</b>	<b>10</b>	<b>86</b>	<b>29</b>

GUARDRAIL SCHEDULE								
LOCATION IL 49	LENGTH	NOTES	GUARDRAIL REMOVAL	TBT TY 1 SP TANG.	SPBGR ATTACHED TO STRUCT.	SPBGR TY. A 6" POSTS	GUARDRAIL MARKER TY. A	HMA STABILIZATION 6"
			FT	EACH	FOOT	FOOT	EACH	SO YD
<b>ILLINOIS COUNTY</b>								
STA. 1222+00 TO STA. 1223+86.5	186.5	BEGIN PROJECT	308	2	50	163	6	88
STA. 1223+86.5 TO STA. 1224+13.5	27.0	S.N. 038-2506	50					
STA. 1224+13.5 TO STA. 1226+30.0	216.5	END PROJECT	200	2	50	125	7	75
<b>TOTAL</b>			<b>558</b>	<b>4</b>	<b>50</b>	<b>287.5</b>	<b>13</b>	<b>163</b>

DELINATOR SCHEDULE	
STATION	EACH
1225+20.22 RT	1
1225+67.04 LT	1
1225+69.94 RT	1
1226+16.95 LT	1
<b>TOTAL</b>	<b>4</b>

SEEDING AND EROSION CONTROL										
LOCATION IL 49	NOTES	LENGTH FOOT	SEEDING CLASS 2A ACRE	MULCH METHOD 2 ACRE	TEMP EROSION CONTROL SEEDING POUNDS	NITROGEN FERTILIZER POUNDS	PHOSPHORUS FERTILIZER POUNDS	POTASSIUM FERTILIZER POUNDS	TEMPORARY DITCH CHECK FOOT	INLET AND PIPE PROTECTION EACH
STA. 1222+00 TO STA. 1223+72.5	BEGIN PROJECT	173	0.18	0.18	71	16	16	16	54	
STA. 1223+72.5 TO STA. 1224+13.5	S.N. 038-2026	41							13	
STA. 1224+13.5 TO STA. 1226+30.0	END PROJECT	217	0.24	0.24	95	21	21	21	68	4
<b>TOTAL</b>			<b>0.42</b>	<b>0.42</b>	<b>166</b>	<b>37</b>	<b>37</b>	<b>37</b>	<b>134</b>	<b>4</b>

EARTH EXCAVATION				
LOCATION	EARTH EXCAVATION (CUTS) CU YD	EARTH EXCAVATION ADJ FOR SHRINKAGE 25% CU YD	EMBANKMENT (FILLS) CU YD	(FURNISHED EX.) EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD
STA. 1222+00 TO STA. 1226+30	277.8	208.3	517	-308.7
<b>TOTALS</b>	<b>278</b>			<b>-309</b>