

REMOVAL SCHEDULE					
LOCATION	ISLAND SURFACE REMOVAL AND REPLACEMENT	EARTH EXCAVATION	COMBINATION CURB AND GUTTER REMOVAL	PAVED SHOULDER REMOVAL	PAVEMENT REMOVAL
	SQ FT	CU YD	FOOT	SQ YD	SQ YD
RAMP A	127.5	24	54	219	614
RAMP B	-	19	-	175	486
RAMP C	127.5	22	54	199	515
RAMP D	-	18	-	165	481
TOTALS	255	83	108	758	2096

PAVEMENT MARKER SCHEDULE		
LOCATION	PRISMATIC CURB REFLECTOR	FLEXIBLE DELINEATOR
	EACH	EACH
RAMP A	11	-
RAMP C	11	-
IL 17 MAINLINE	-	4
TOTALS	22	4

RAMP RECONSTRUCTION SCHEDULE						
LOCATION	PCC PAVEMENT 8" (JOINTED)	PCC SHOULDER 8"	DRILL & GROUT #6 TIE BARS	DRIL & GROUT DOWEL BARS	COMBINATION CURB AND GUTTER TYPE M-6.06	ISLAND SURFACE REMOVAL & REPLACEMENT
	SQ YD	SQ YD	EACH	EACH	FOOT	SQ FT
RAMP A	614	219	83	16	54	128
RAMP B	486	175	80	16	-	-
RAMP C	515	199	74	16	54	128
RAMP D	481	165	80	16	-	-
TOTALS	2096	758	317	64	108	256

AGGREGATE SCHEDULE		
LOCATION	SUBBASE GRANULAR MATL. 4"	AGGREGATE SHOULDER TYPE B
	TON	TON
RAMP A	192	12
RAMP B	149	9
RAMP C	165	10
RAMP D	146	11
TOTALS	652	42

PAVEMENT MARKING SCHEDULE MODIFIED URETHANE					
LOCATION	L&S WHITE	4" WHITE	4" YELLOW	8" WHITE	12" WHITE
	FOOT	FOOT	FOOT	FOOT	FOOT
RAMP A	39	221	141	144	84
RAMP B	-	172	115	-	-
RAMP C	39	198	136	114	47
RAMP D	-	169	114	-	-