

CODE NO.	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	80/20 FED/STATE	
				CONSTRUCTION CODE	
				ROADWAY 0004	BRIDGE 0011
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	78	78	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	130	130	
20100500	TREE REMOVAL, ACRES	ACRE	2	2	
20200100	EARTH EXCAVATION	CU YD	17,695	17,695	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	79	79	
21001000	GEO TECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	66	66	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	11,943	11,943	
25000210	SEEDING, CLASS 2A	ACRE	1.25	1.25	
25000300	SEEDING, CLASS 3	ACRE	3.00	3.00	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	370	370	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	370	370	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	370	370	
25100115	MULCH, METHOD 2	ACRE	2.5	2.50	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	8,585	8,585	

FILE NAME *	USER NAME * j_dwan	DESIGNED - MVM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.P. ROUTE 698 (IL 89) SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
v:\transportation\2013\cadd\sheet\0468	08-shs-S00.dgn	DRAWN - JCW	REVISED -					698	025V8R1BR	MARSHALL	148	5
PLOT SCALE * 2.00/200 FT / IN.	CHECKED - AWM	REVISIED -			SCALE: 3=1	SHEET NO. 1 OF 9 SHEETS	STA. N/A	TO STA. N/A	CONTRACT NO. 68580			
PLOT DATE * 7/25/2013	DATE - JULY 24, 2013	REVISED -			ILLINOIS FED. AID PROJECT							