

CODE NO.	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	80/20 FED / STATE CONSTRUCTION CODE	
				ROADWAY 0004	BRIDGE 0011
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	822	822	
28000315	AGGREGATE DITCH CHECKS	TON	364	364	
28000400	PERIMETER EROSION BARRIER	FOOT	2,485	2,485	
28000500	INLET AND PIPE PROTECTION	EACH	6	6	
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	50	50	
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	2,667	817	1,850
28200200	FILTER FABRIC	SQ YD	2,717	867	1,850
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	1,890	1,890	
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	1,285	1,285	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	108	108	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50	50	
40600285	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	POUND	16,000	16,000	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	566	566	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	174	174	

FILE NAME : 0468580-ht-500.dgn	USER NAME : jacobsmr	DESIGNED - MVM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.P. ROUTE 698 (IL 89) SUMMARY OF QUANTITIES			F.A.P. RTE. 698	SECTION (125VBR)BR	COUNTY MARSHALL	TOTAL SHEETS 148	SHEET NO. 6
		DRAWN - JCW	REVISED -		SCALE: 1"=1'	SHEET NO. 2 OF 9 SHEETS	STA. N/A	TO STA. N/A	CONTRACT NO. 68580			
		CHECKED - AWM	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE - JULY 24, 2013	REVISED -									