CODE NO.	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	80/20 FED/ STATE CONSTRUCTION CODE ROADWAY 0004	BRIDGE 0011
50800530	MECHANICAL SPLICERS	EACH	848		848
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	1,176		1,176
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	3,944		3,944
51202305	DRIVING PILES	FOOT	5,120		5,120
51203200	TEST PILE METAL SHELLS	EACH	8		8
51500100	NAME PLATES	EACH	1		1
51204650	PILE SHOES	EACH	134		134
52000110	PREFORMED JOINT STRIP SEAL	FOOT	108		108
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24		24
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	18		18
52100505	ANCHOR BOLTS, 5/8"	EACH	24		24
52100510	ANCHOR BOLTS, 3/4"	EACH	24		24
52100520	ANCHOR BOLTS, 1"	EACH	24		24
52100530	ANCHOR BOLTS, 1-1/4"	EACH	36		36