

HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT

STATION TO STATION	SIDE	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT SQ YD
FAP ROUTE 698 (IL 89)		
275+00.00   275+30.00	LT & RT	86.7
308+20.00   308+50.00	LT & RT	86.7
TOTAL		173.4
USE		174

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

STATION TO STATION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH
FAP ROUTE 698 (IL 89)	
275+54 TO 307+71	34
TOTAL	34
USE	34

RAISED REFLECTIVE PAVEMENT MARKERS

STATION TO STATION	RAISED REFLECTIVE PAVEMENT MARKER EACH	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) EACH
FAP ROUTE 698 (IL 89)		
275+00.00 TO 293+93.66	24	
293+93.66 TO 301+60.99		10
301+60.99 TO 308+50.00	9	
TOTAL	33	10
USE	33	10

GUARDRAIL SCHEDULE

STATION TO STATION	SIDE	STEEL PLATE BEAM GUARDRAIL, TYPE A FOOT	TRAFFIC BARRIER TERMINALS EACH	
			TYPE 1, SPECIAL (TANGENT)	TYPE 6
FAP ROUTE 698 (IL 89)				
282+03.50 TO 285+67.50	RT	262.5	2	
282+66.26 TO 294+19.76	LT	1,050.0	1	1
288+51.10 TO 294+17.90	RT	475.0	1	1
301+34.82 TO 304+92.97	RT	262.5	1	1
301+34.82 TO 305+80.47	LT	350.0	1	1
TOTALS		2,400	6	4
USE		2,400	6	4

PAVEMENT REMOVAL

STATION TO STATION	SIDE	PAVEMENT REMOVAL SQ YD
FAP ROUTE 698 (IL 89)		
290+80.00   294+69.13	LT & RT	1,124.2
301+08.06   302+85.00	LT & RT	511.2
TOTAL		1,635.4
USE		1,636

PERMANENT SURVEY MARKERS, TYPE 1

STATION	DESCRIPTION	PERMANENT SURVEY MARKERS, TYPE 1 EACH
FAP ROUTE 698 (IL 89)		
275+00.00	POT	1
277+95.58	PC	1
296+18.27	PT	1
306+00	POT	1
NW CORNER OF BRIDGE	BM	1
TOTAL		5
USE		5

GUARDRAIL/ BARRIER WALL MARKERS

STATION TO STATION	SIDE	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKER DIRECT APPLIED
FAP ROUTE 698 (IL 89)				
282+03.50 TO 285+67.50	RT	4		2
282+62.50 TO 305+78.47	LT	10	4	2
288+43.39 TO 304+90.97	RT	6	4	2
TOTALS		20	8	6
USE		20	8	6

GUARDRAIL AGGREGATE EROSION CONTROL

STATION TO STATION	SIDE	GUARDRAIL AGGREGATE EROSION CONTROL TON
FAP ROUTE 698 (IL 89)		
281+65.40   286+00.43	RT	113.6
282+27.27   294+17.24	LT	310.8
288+36.99   294+15.41	RT	151.1
301+37.32   305+27.59	RT	101.9
301+37.32   306+12.99	LT	124.2
TOTAL		801.6
USE		802

ENTRANCE SCHEDULE

LOCATION	SIDE	WIDTH	THICKNESS	AGGREGATE SURFACE COURSE, TYPE B TON
FAP ROUTE 698 (IL 89)				
279+75.00	RT	20'	6"	14
279+97.05	LT	16'	6"	12
281+62.00	LT	24'	6"	19
288+12.68	RT	30'	8"	30
306+80.00	LT	20'	6"	33
TOTAL				98
USE				108

RIPRAP SCHEDULE

LOCATION	SIDE	WIDTH	LENGTH	STONE DUMPED RIPRAP		FILTER FABRIC SO YD
				CLASS A4	CLASS A3	
				SQ YD		
FAP ROUTE 698 (IL 89)						
279+43.00	ENTRANCE	RT	8	37.8		33.5
283+00	284+25	LT	17	125	237.0	237.0
283+50	284+25	RT	17	75	142.0	142.0
290+77	290+83	LT	6	6		4.0
290+77	290+83	RT	6	6		4.0
302+82	302+88	LT	6	6		4.0
302+82	302+88	RT	6	6		4.0
303+00	304+00	LT	14	100	156.0	156.0
303+00	304+00	RT	15	100	167.0	167.0
TOTAL					702.0	751.5
USE					702	752

HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"

STATION TO STATION	SIDE	PAVEMENT REMOVAL SQ YD
FAP ROUTE 698 (IL 89)		
275+30.00   290+80.00	LT & RT	4,477.8
302+85.00   308+20.00	LT & RT	1,545.6
TOTAL		6,023.4
USE		6,024

PAVED SHOULDER REMOVAL

STATION TO STATION	SIDE	PAVED SHOULDER REMOVAL SQ YD
FAP ROUTE 698 (IL 89)		
285+33.09   286+75.00	LT	54.1
285+33.84   286+75.00	RT	41.5
302+85.00   306+12.99	LT	123.8
302+85.00   305+27.59	RT	81.8
TOTAL		301.2
USE		302

PAVING SCHEDULE

STATION TO STATION	PORTLAND CEMENT CONCRETE BASE COURSE, 8"	AGGREGATE BASE COURSE TYPE A, 12"	HOT-MIX ASPHALT SHOULDERS, 8"	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	HOT-MIX ASPHALT SHOULDERS	AGGREGATE SHOULDERS, TYPE B
	SQ YD				TON					
FAP ROUTE 698 (IL 89)										
275+00.00   290+80.00			1,476.6		10,300	366.20	1,342.7	412.8		201.0
290+80.00   293+93.66	920.7	1,348.7	343.4		1,380	51.30		81.9		
293+93.66   293+99.66			5.3	113.3						
301+54.99   301+60.99			5.6	113.3						
301+60.99   302+85.00	364.0	541.0	131.7		540	20.30		32.4		
302+85.00   308+50.00			315.6		2,620	127.60	182.6	147.6	37.9	67.8
TOTAL	1,284.7	1,889.7	2,278.2	226.6	14,800	565.4	1,525.3	674.7	37.9	268.8
USE	1,285	1,890	2,279	227	16,000	566	1,526	675	38	269

MODIFIED URETHANE PAVEMENT MARKING

STATION TO STATION	SIDE	YELLOW SKIP DASH	YELLOW DOUBLE SOLID 4"	YELLOW SOLID	WHITE SOLID 6"
FAP ROUTE 698 (IL 89)					
275+00.00   306+50.00	CL		6,300.0		
275+00.00   308+50.00	LT&RT				6,700.0
306+50.00   308+50.00	CL	50.0		200.0	
TOTAL			6,550.0		6,700.0
USE			6,550		6,700