


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE	90% FED 10% STATE TRAINEES	100% STATE ROADWAY
				0004	0011	0011	0042	0004
				RURAL	048-0090	048-0091	RURAL	RURAL
50300255	CONCRETE SUPERSTRUCTURE	CU YD	694.7		352.2	342.5		
50300260	BRIDGE DECK GROOVING	SQ YD	1457		736	721		
50300300	PROTECTIVE COAT	SQ YD	1751		897	854		
50400745	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 72"	FOOT	1234.5		629	605.5		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	171880		87610	84270		
50800515	BAR SPLICERS	EACH	1149		579	570		
51201710	FURNISHING STEEL PILES HP12X84	FOOT	1515		765	750		
51202305	DRIVING PILES	FOOT	1515		765	750		
51203710	TEST PILE STEEL HP12X84	EACH	4		2	2		
51500100	NAME PLATES	EACH	2		1	1		
54210182	PIPE ELBOW, 12"	EACH	16	16				
54213447	END SECTIONS 12"	EACH	8	8				
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	268		132	136		
60100945	PIPE DRAINS 12"	FOOT	386	386				

* DENOTES SPECIALTY ITEM

FILE NAME : \\D4-174-ManderanCreek-Combined-sh1005-5000.dwg	DESIGNED - JCP	REVISED -	 <small>46 WEST FLATION STREET CHICAGO, ILLINOIS 60611-2019 TEL: 312.434.8100 FAX: 312.539.3137 WEB: www.sepstein.com</small>	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT TIME : 1:20:51 PM	CHECKED - GAO	REVISED -							74	48-[[258]BR, BR-1]	KNOX	131	5
PLOT DATE : 8/12/2014	DATE - 08/01/14	REVISED -			SCALE: N/A	SHEET NO. 3 OF 6 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		CONTRACT NO. 68B85		