

**GENERAL NOTES**


1. Reinforcement bars designated (E) shall be epoxy coated.
2. Layout of slope protection system may be varied to suit ground conditions in the field as directed by the Engineer.
3. Slipforming of the parapets is not allowed.

**INDEX OF SHEETS**

- S1 General Plan and Elevation
- S2 General Data
- S3 Substructure Layout
- S4 Stage Construction Details and Temp. Soil Retention System
- S5 Temporary Concrete Barrier for Stage Construction
- S6 Top of Deck
- S7 Top of Deck Elevations I
- S8 Top of Deck Elevations II
- S9 Top of Deck Elevations III
- S10 Top of North Approach Slab Elevations
- S11 Top of South Approach Slab Elevations
- S12 Superstructure Plan and Cross Section
- S13 Superstructure Details
- S14 Diaphragm Details
- S15 Bridge Approach Slab
- S16 Bridge Approach Slab Details
- S17 Framing Plan
- S18 72" PPC Bulb T-Beam
- S19 72" PPC Bulb T-Beam Details
- S20 Abutment Plan and Elevation
- S21 Abutment Details
- S22 HP Pile Details
- S23 Drainage Scupper DS-II
- S24 Bar Splicer Assembly and Mechanical Splicer Details
- S25 Boring Logs

**TOTAL BILL OF MATERIAL**

ITEMS	UNITS	SUPERSTRUCTURE	SUBSTRUCTURE	TOTAL
Stone RipRap, Class A4	SQ YD		1,673	1,673
Filter Fabric	SQ YD		1,673	1,673
Removal of Existing Structures	EACH		1	1
Structure Excavation	CU YD		804	804
Concrete Structures	CU YD		84.2	84.2
Concrete Superstructure	CU YD	352.2		352.2
Bridge Deck Grooving	SQ YD	736		736
Protective Coat	SQ YD	897		897
Furnishing and Erecting Precast Prestressed Concrete Bulb T-Beams 72"	FOOT	629		629
Reinforcement Bars, Epoxy Coated	POUND	71,340	16,270	87,610
Bar Splicers	EACH	479	100	579
Furnishing Steel Piles HPI2x84	FOOT		765	765
Driving Piles	FOOT		765	765
Test Pile Steel HPI2x84	EACH		2	2
Name Plates	EACH	1		1
Geocomposite Wall Drain	SQ YD		132	132
Granular Backfill for Structures	CU YD		318.2	318.2
Drainage Scuppers, DS-II	EACH	8		8
Pipe Underdrains for Structures 4"	FOOT		202	202
Temporary Soil Retention System	SQ FT		188	188



Note:

All drainage system components shall extend to 2'-0" from the end of each wingwall except an outlet pipe shall extend until intersecting with the side slopes. The pipes shall drain into concrete headwalls. (See Article 601.05 of the Standard Specifications and Highway Standard 601101).

\* Included in the cost of Pipe Underdrain for Structures. (See Special Provisions).

**SECTION THRU INTEGRAL ABUTMENT**  
(Horiz. dim. @ Rt. L's)

FILE NAME = ... \0480090-68084-002-Gen_data.dgn	DESIGNED <i>EV</i> DRAWN <i>JCP</i>	REVISED - REVISED -	 800 WEST FULTON STREET CHICAGO, ILLINOIS 60611-1259 TEL 312 454 9100 FAX 312 559 1217 WEB www.sepstein.com	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL DATA STRUCTURE NO. 048-0090	F.A.I. RTE. 74	SECTION 48-[125B]BR, BR-1J	COUNTY KNOX	TOTAL SHEETS 131	SHEET NO. 23
PLOT TIME = 4:31:08 PM	CHECKED <i>PC</i>	REVISED -				CONTRACT NO. 68B85				
PLOT DATE = 7/30/2014	DATE 05 03 2013	REVISED -				SHEET NO. S2 OF S25 SHEETS				