


**BEAM 6**

| Location        | Station   | Offset | Theoretical Grade Elevations | Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding |
|-----------------|-----------|--------|------------------------------|---|
| BK N. ABUT.     | 416+64.02 | -15.36 | 755.46                       | 755.46  |
| CL N. ABUT.     | 416+65.92 | -15.35 | 755.46                       | 755.46  |
| A               | 416+75.92 | -15.31 | 755.43                       | 755.45  |
| B               | 416+85.92 | -15.28 | 755.40                       | 755.45  |
| C               | 416+95.92 | -15.26 | 755.39                       | 755.45  |
| D               | 417+05.92 | -15.24 | 755.38                       | 755.45  |
| E               | 417+15.92 | -15.24 | 755.38                       | 755.46  |
| F               | 417+25.92 | -15.24 | 755.38                       | 755.45  |
| G               | 417+35.92 | -15.25 | 755.40                       | 755.46  |
| H               | 417+45.92 | -15.26 | 755.42                       | 755.46  |
| I               | 417+55.92 | -15.29 | 755.44                       | 755.47  |
| CL BRG. S. ABUT | 417+65.85 | -15.32 | 755.48                       | 755.48  |
| BK S. ABUT      | 417+67.74 | -15.33 | 755.49                       | 755.49  |

|  |  |                        |   |   |  |                            |                    |        |                           |              |
|--|--|------------------------|---|---|--|----------------------------|--------------------|--------|---------------------------|--------------|
| FILE NAME =<br>...\\0480091-68084-009-TOS.Elevs3.dgn | DESIGNED <i>EV</i><br>DRAWN <i>JCP</i> | REVISED -<br>REVISED - | <br>800 WEST FULTON STREET<br>CHICAGO, ILLINOIS 60611-1299<br>TEL 312 454 9100<br>FAX 312 555 1217<br>WEB www.sepstein.com | STATE OF ILLINOIS<br>DEPARTMENT OF TRANSPORTATION | TOP OF DECK ELEVATIONS III<br>STRUCTURE NO. 048-0091 | F.A.I.<br>RTE.             | SECTION            | COUNTY | TOTAL<br>SHEETS           | SHEET<br>NO. |
| PLOT TIME = 4:31:55 PM                               | CHECKED <i>PC</i>                      | REVISED -              |   |   |  | 74                         | 48-[125B]BR, BR-1J | KNOX   | 131                       | 55           |
| PLOT DATE = 7/30/2014                                | DATE <i>05 03 2013</i>                 | REVISED -              |   |   |  | SHEET NO. S9 OF S25 SHEETS |                    |        | ILLINOIS FED. AID PROJECT |              |
|  |  |                        |   |   |  | CONTRACT NO. 68B85         |                    |        |                           |              |