CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE 0044 PEORIA 100% STATE
20200100	EARTH EXCAVATION	CU YD	147	147
20400800	FURNISHED EXCAVATION	CU YD	101	101
21101625	TOPSOIL FURNISH AND PLACE 6"	SQ YD	220	220
25000305	SEEDING CLASS 3A	ACRE	0.1	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9
25100630	EROSION CONTROL BLANKET	SQ YD	220	220
25100900	TURF REINFORCEMENT MAT	SQ YD	768	768
60107800	PIPE UNDERDRAIN 8"	FOOT	175	175
* 63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	600	600
67100100	MOBILIZATION	L SUM	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	0.5	0.5
Z0001002	GUARDRAIL AGGREGATE EROSION CONTROL	TON	122	122
Z0020805	EROSION CONTROL CURB REMOVAL	FOOT	600	600

* SPECIALTY ITEM

FILE NAME = day labor1.dgn	USER NAME = aubreyga	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. 74	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN -	REVISED -			RTE. I-74	(72-4)I-3	PEORIA	10 / 3
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -					CONTRACT NO. 68C31	
	PLOT DATE = 8/18/2014	DATE -	REVISED -				ILLINOIS	FED. AID PROJECT	