LOCATION	REMOVE AND RE-ERECT SPBGR TYPE A	GUARDRAIL AGG EROSION CONTROL	EROSION CONTROL CURB REMOVAL
	FOOT	TON	FOOT
75+00 TO 81+00	600	122	600
TOTAL	600	122	600

MOBILIZATION	L SUM
JOB SITE	1
TOTAL	1

TRAFFIC CONTROL & PROTECTION STD 701406	L SUM
JOB SITE	1
TOTAL	1

LOCATION	EARTH EXCAVATION	FOR INFO ONLY EARTH EXCAV ADJUSTED TO 25% SHRINKAGE	FOR INFO ONLY EMBANKMENT	FURNISHED EXCAVATION	TURF REINF MAT	pipe under-drain 8''
	CU. YD.	CU. YD.	CU. YD.	CU. YD.	SQ. YD.	FOOT
78+00 TO 79+70	147	163	320	101	768	175
TOTAL	147	163	320	101	768	175

CHANGEABLE MESSAGE SIGN	CAL MO
JOB SITE	0.5
*TOTAL	0.5

* 1 SIGN FOR 2 WEEKS

LOCATION	SEEDING CLASS 3 A	TOPSOIL FURNISH & PLACE 6''	NITROGEN FERTILIZER NUTRIENT	NITROGEN FERTILIZER NUTRIENT	NITROGEN FERTILIZER NUTRIENT	EROSION CONTROL BLANKET
	ACRE	SQ YD	POUND	POUND	POUND	SQ YD
78+00 TO 80+00	0.1	220	9	9	9	220
TOTAL	0.1	220	9	9	9	220