

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80%/20% FED/STATE ROADWAY	90%/10% SAFETY ROADWAY
				0005	0021
				RURAL	RURAL
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	913		913
28100107	STONE RIPRAP, CLASS A4	SQ YD	8	8	
35800100	PREPARATION OF BASE	SQ YD	24	24	
40200600	AGGREGATE SURFACE COURSE, TYPE B	TON	32	32	
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	17,247	17,247	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	75	75	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,457	1,457	
40600990	TEMPORARY RAMP	SQ YD	352	352	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	10,777	10,777	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	7,185	7,185	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	159	159	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	85,530	85,530	
44004250	PAVED SHOULDER REMOVAL	SQ YD	912		912
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3,331		3,331

FILE NAME : e:\pwork\p1dot\pricess\023988\0672	USER NAME : pricess	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
DB4-ent-500.dgn	PLOT SCALE : 100.0000 / 1 in.	DRAWN -	REVISED -						325	*	CHRISTIAN	28	3
Default	PLOT DATE : Aug-14-2014 09:11:00PM	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 72E04		
		DATE -	REVISED -										