

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				ROADWAY
				0005
20200100	EARTH EXCAVATION	CU YD	450	450
20200600	EXCAVATING AND GRADING EXISTING SHOULDERS	UNIT	34	34
20400800	FURNISHED EXCAVATION	CU YD	453	453
21400100	GRADING AND SHAPING DITCHES	FOOT	172	172
25000210	SEEDING, CLASS 2A	ACRE	2	2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	180	180
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	180	180
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	180	180
25000700	AGRICULTURAL GROUND LIMESTONE	TON	4	4
25100115	MULCH, METHOD 2	ACRE	2	2
28000315	AGGREGATE DITCH CHECKS	TON	38	38
28000400	PERIMETER EROSION BARRIER	FOOT	431	431
28100107	STONE RIPRAP, CLASS A4	SQ YD	77	77
28200200	FILTER FABRIC	SQ YD	77	77

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				ROADWAY
				0005
35101400	AGGREGATE BASE COURSE, TYPE B	TON	42	42
35800100	PREPARATION OF BASE	SQ YD	673	673
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	37	37
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	121,000	121,000
<del>40600300</del>	<del>AGGREGATE (PRIME COAT)</del>	<del>TON</del>	<del>352</del>	<del>352</del>
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	3,683	3,683
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,777	1,777
40600990	TEMPORARY RAMP	SQ YD	105	105
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	5,095	5,095
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	7,758	7,758
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	354	354
44000158	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"	SQ YD	5,336	5,336
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	1,150	1,150
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	825	825