

FENCE REMOVAL

| TYP. SEC. # | LOCATION | QUANTITY (FOOT) |
|-------------|----------------------------|-----------------|
| | (AREA A) | |
| | [F. A. P. 510 (IL 96)] | |
| 28 | 7+35.00 TO 898.00 LT | 163 |
| 29 | 12+43.00 TO 14+43.00 LT | 200 |
| | | |
| | PROJECT TOTAL | 363 |

TEMPORARY RAMP

| TYP. SEC. # | LOCATION | QUANTITY (SQ YD) |
|-------------|------------------------------------|--------------------|
| | (AREA A) | |
| | [F. A. P. 510 (IL 96)] | |
| (1) | STA. 26+36.00 TO STA. 26+41.00 | 14.44 |
| | TOTAL AREA A | 14.44 |
| | (AREA B) | |
| | [F. A. P. 685 (IL 9/IL 96)] | |
| (12) | STA. 139+95.00 TO STA. 140+00.00 | 12.22 |
| | PAVING OMISSION | |
| | STA. 140+00.00 TO STA. 154+00.00 | |
| (13) | STA. 154+00.00 TO STA. 154+05.00 | 12.22 |
| | | |
| (20) | STA. 230+55.81 TO STA. 230+60.81 | 18.33 |
| | (BRIDGE OMISSION) S. N. 034-0009 | |
| | STA. 230+60.81 TO STA. 232+39.81 | |
| (21) | STA. 232+39.81 TO STA. 232+44.81 | 18.33 |
| (27) | STA. 330+31.62 TO STA. 330+36.62 | 17.78 |
| | TOTAL AREA B | 78.89 |
| | (AREA C) | |
| | [F. A. P. 685 (IL 9)] | |
| (28) | STA. 7+35.17 TO STA. 7+40.17 | 11.11 |
| | TOTAL AREA C | 11.11 |
| | | |
| | PROJECT TOTAL | 105 |

INCIDENTAL HOT-MIX ASPHALT SURFACING

| LOCATION | QUANTITY (TON) |
|-----------------------------------|------------------|
| F. A. P. 685 & 510 (IL 9/IL 96) | |
| EXIST HMA ENTR | 196.06 |
| SIDE ROADS | 157.24 |
| SEE ENTRANCE SCHEDULE DETAILS | |
| PROJECT TOTAL | 354 |

AGGREGATE SURFACE COURSE, TYPE B

| LOCATION | QUANTITY (TON) |
|-----------------------------------|------------------|
| F. A. P. 685 & 510 (IL 9/IL 96) | |
| Quantity for HMA PE's and CE's | 36.56 |
| SEE ENTRANCE SCHEDULE DETAILS | |
| PROJECT TOTAL | 37 |

PREPARATION OF BASE

| LOCATION | QUANTITY (SQ YD) |
|---|--------------------|
| F. A. P. 685 & 510 (IL 9/IL 96) | |
| TOTAL AREA FOR 24 ENTRANCES & SIDEROADS | 672.22 |
| SEE ENTRANCE SCHEDULE DETAILS | |
| PROJECT TOTAL | 673 |

AGGREGATE BASE COURSE, TYPE B

| LOCATION | QUANTITY (TON) |
|------------------------------------|------------------|
| F. A. P. 685 (IL 9/IL 96) | |
| Quantity for HMA PE STA. 174+87.00 | 42.00 |
| | |
| PROJECT TOTAL | 42 |