

EARTH EXCAVATION

TYP. SEC. #	LOCATION		EARTH EXCAVATION	FURNISHED EXCAVATION
			(CU YD)	(CU YD)
	(AREA B)			
	[F. A. P. 685 (IL 9/IL 96)]			
	STA. 43+30.89	TO STA. 46+00.00		3.62
14-16	STA. 166+00.00	TO STA. 172+50.00	169.85	145.10
(17)	STA. 172+50.00	TO STA. 179+00.00	154.25	318.72
(17)	STA. 179+00.00	TO STA. 184+50.00	71.12	-11.73
	(AREA A)			
	[F. A. P. 510 (IL 96)]			
	STA. 0+50.00	TO STA. 4+50.00	40.92	-25.86
	STA. 179+00.00	TO STA. 184+50.00	12.84	26.40
	PROJECT TOTAL		450	453

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION		RRPM (EACH)	RRPM REMOVAL (EACH)
F. A. P. 685 & 510 (IL 9/96)			
STA. 0+00.00	TO STA. 26+41.00	34	34
STA. 31+88.68	TO STA. 140+00.00	135	135
STA. 154+00.00	TO STA. 230+60.81	97	97
STA. 232+39.81	TO STA. 330+36.62	123	123
STA. 7+35.17	TO STA. 31+70.33	31	31
PROJECT TOTAL		420	420

RIPRAP SCHEDULE

TYP. SEC. #	LOCATION		FILTER FABRIC (SQ YD)	STONE RIPRAP, CLASS A4 (SQ YD)
	(AREA B) (MEASURED USING CADD)			
	[F. A. P. 685 (IL 9/IL 96)]			
(7B)	STA. 43+02.00	TO STA. 43+25.00	37.60	37.60
(7B)	STA. 43+13.00	TO STA. 43+40.00	38.83	38.83
	PROJECT TOTAL		77	77

HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N50

LOCATION		AVERAGE THICKNESS (FOOT)	QUANTITY (TONS)
F. A. P. 685 & 510 (IL 9/96)			
STA. 166+25.00	TO STA. 167+75.00	1.0	246.40
STA. 167+75.00	TO STA. 172+51.56	2.0	1,565.66
STA. 172+51.56 (BK) = STA. 172+51.01 (AH)			
STA. 172+51.01	TO STA. 181+50.00	2.0	2,953.48
STA. 181+50.00	TO STA. 183+50.00	1.0	328.53
PROJECT TOTAL			5,095

PRECAST REINFORCED CONCRETE
FLARED END SECTIONS, 30"

TYP. SEC. #	LOCATION		QUANTITY (EACH)
	(AREA B)		
	[F. A. P. 685 (IL 9/IL 96)]		
16	STA. 173+01.00	31.89' LT	1
16	STA. 173+01.00	27.97' RT	1
16	STA. 176+02.00	29.26' LT	1
16	STA. 176+02.00	26.83' RT	1
	PROJECT TOTAL		4

PIPE CULVERT

TYP. SEC. #	LOCATION		OFFSET		METAL END SECTIONS 15" (EA)	PIPE CULV REM (FOOT)	PIPE CULV, CL D, T1 15" (FOOT)
			LT	RT			
	F. A. P. 510 (IL 96) AREA A						
3	STA. 1+84.84	TO STA. 3+87.34	LT 30.10	RT 29.30	2	285.30	202.50
	F. A. P. 685 (IL 9/IL 96) AREA B						
14	STA. 167+03.00	TO STA. 167+36.00	RT 30.78	RT 30.87	2	33.00	33.00
17	STA. 180+21.00	TO STA. 180+43.00	RT 27.63	RT 27.59	2	21.70	21.70
	PROJECT TOTAL				6	340	257