

STORM SEWERS, CLASS B, TYPE 1 12"

TYP. SEC. #	LOCATION	QUANTITY (FOOT)
	F. A. P. 510 (IL 96) AREA A	
	APPOX. LOCATION DETERMINED IN FIELD	
3	STA. 4+70.14, 35.82' LT	10
PROJECT TOTAL		10

PIPE CULVERTS, CLASS A, TY 1 30"

TYP. SEC. #	LOCATION	QUANTITY (FOOT)
	F. A. P. 685 (IL 9/IL 96) AREA B	
16	STA. 173+01.00	96
16	STA. 176+02.00	96
PROJECT TOTAL		192

PERMANENT SURVEY MARKERS

TYP. SEC. #	LOCATION	QUANTITY (EACH)
	[F. A. P. 685 (IL 9/IL 96)]	
(16)	STA. 175+97.00	1
(20)	STA. 230+49.00	1
PROJECT TOTAL		2

GRADING AND SHAPING SHOULDERS

TYP. SEC. #	LOCATION	QUANTITY (UNIT)
	[F. A. P. 685 (IL 9/IL 96)]	
(31)	STA. 30+63.00 TO STA. 31+59.00 LT	1.25
(20)	STA. 30+80.00 TO STA. 31+59.00 RT	0.83
PROJECT TOTAL		2

AGGREGATE DITCH CHECKS

TYP. SEC. #	LOCATION	QUANTITY (TON)
	(AREA B)	
	[F. A. P. 685 (IL 96)]	
16	STA. 172+91.00 LT	3.72
16	STA. 172+91.00 RT	3.72
16	STA. 173+11.00 RT	3.72
16	STA. 175+55.00 LT	3.72
16	STA. 175+80.00 RT	3.72
16	STA. 175+80.00 LT	3.72
16	STA. 175+95.00 LT	3.72
16	STA. 176+11.00 LT	3.72
16	STA. 176+37.00 RT	3.72
16	STA. 176+37.00 LT	3.72
PROJECT TOTAL		37.20

INLETS, TYPE B, TYPE 8 GRATE

TYP. SEC. #	LOCATION	QUANTITY (EACH)
	(AREA A)	
	[F. A. P. 510 (IL 96)]	
3	STA. 4+70.14, 35.82' LT	1
PROJECT TOTAL		1

GRADING AND SHAPING DITCHES

TYP. SEC. #	LOCATION	QUANTITY (FOOT)
	F. A. P. 510 (IL 96) AREA A	
3	STA. 0+98.94 TO 1+84.84 LT	85.9
3	STA. 3+87.34 TO 4+70.14 LT	85.9
PROJECT TOTAL		172

FILE NAME =	USER NAME = sparksgw	DESIGNED - JWC	REVISED -
ct:\pw\work\p\dot\sparksgw\10296720\0672F32-sht-schedule.dgn		DRAWN - JWC	REVISED -
	PLOT SCALE = 100.0000' / 1in.	CHECKED - MSD	REVISED -
	PLOT DATE = Jun-06-2014 10:35:01AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: 50 SHEET 5 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
••	(119)RS-11,(113)RS-6	HANCOCK	95	10
CONTRACT NO. 72F32			ILLINOIS FED. AID PROJECT	