

STRIPING SCHEDULE

LOCATION			PAINT PAVEMENT MARKING			THERMOPLASTIC PAVEMENT MARKING		PREFORMED PLASTIC PAVEMENT MARKING INLAID				SHORT TERM PAVT MARK FOOT	WORK ZONE PAVT MARK REMOVAL SQ FT
			LINE 5"			LINE 5"	LINE 6"	LINE 5"	LINE 8"	LINE 12"	LINE 24"		
STATION	TO	STATION	WHITE FOOT	YELLOW TYPE	WHITE FOOT	WHITE FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	WHITE FOOT		
FAP 510 ( IL 96) AREA A													
26+41.00	TO	18+50.00	1,582.0	SKIP	200.0							237.30	26.37
18+50.00	TO	0+00.00				3700.0	108.0	460.0	435.5	29.6	30.0	555.00	61.67
STA. EON. #1	STA. 0+00.00 (BK) = 31+88.68 (AH)												
F. A. P. 685 ( IL 9/IL 96) AREA "B"													
31+88.68	TO	36+00.00				822.6		100.0				123.40	13.71
36+00.00	TO	42+87.73	1,375.5	SKIP	170.0							206.32	22.92
STA. EON. #2	Sta. 42+87.73 (BK) = 42+89.01 (AH)												
42+89.01	TO	136+94.64	18,811.3	SKIP	2,350.0							2,821.69	313.52
STA. EON. #3	STA. 136+94.64 (BK) = 137+00.00 (AH)												
137+00.00	TO	140+00.00	600.0	SKIP	80.0							90.0	10.0
OMISSION	Sta. 140+00.00 TO 154+00.00												
154+00.00	TO	165+00.00	2,200.0	SKIP/SOLID	1,380.0							330.00	36.67
165+00.00	TO	172+51.56	1,503.1	SKIP	190.0							225.47	25.05
STA. EON. #4	STA. 172+51.56 (BK) = 172+51.07 (AH)												
172+51.07	TO	179+00.00	1,297.9	SKIP	160.0							194.68	21.63
179+00.00	TO	195+00.00	3,200.0	SKIP/SOLID	2,000.0							480.00	53.33
195+00.00	TO	230+60.81	7,121.6	SKIP	890.0							1,068.24	118.69
BRIDGE	STA. 230+60.81 TO 232+39.81												
232+39.81	TO	239+00.00	1,320.4	SKIP	170.0							198.06	22.01
239+00.00	TO	240+12.38	224.8	SKIP/SOLID	132.4							33.71	3.75
STA. EON. #5	STA. 240+12.38 (BK) = 240+11.35 (AH)												
240+11.35	TO	259+00.00	3,777.3	SKIP/SOLID	2,348.7							566.60	62.96
259+00.00	TO	264+00.00	1,000.0	SKIP	130.0							150.00	16.67
264+00.00	TO	271+00.00	1,400.0	SKIP/SOLID	880.0							210.00	23.33
271+00.00	TO	279+00.00	1,600.0	DBL SOLID	1,600.0							240.00	26.67
279+00.00	TO	283+00.00	800.0	SKIP/SOLID	500.0							120.00	13.33
283+00.00	TO	286+00.00	600.0	SKIP	80.0							90.00	10.00
286+00.00	TO	292+00.00	1,200.0	SKIP/SOLID	750.0							180.00	20.00
292+00.00	TO	295+00.00	600.0	SKIP	80.0							90.00	10.00
295+00.00	TO	299+00.00	800.0	SKIP/SOLID	500.0							120.00	13.33
299+00.00	TO	300+00.00	200.0	SKIP	30.0							30.00	3.33
300+00.00	TO	322+00.00	4,400.0	SKIP/SOLID	2,740.0							660.00	73.33
322+00.00	TO	327+00.00	1,000.0	DBL SOLID	1,000.0							150.00	16.67
327+00.00	TO	330+36.62	673.2	SKIP/SOLID	416.6							100.99	11.22
7+35.17	TO	23+02.04	3,133.7	SKIP	390.0							470.06	52.23
STA. EON. #6	STA. 23+02.09 (BK) = 23+00.00 (AH)												
23+00.00	TO	31+24.43	1,648.9	SKIP	210.0							247.33	27.48
PROJECT TOTAL =			61,670		19,218	4,523	108	560	436	30	30	9,929	1,104