

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				ROADWAY
				0005
				S. N.
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	136	136
35800100	PREPARATION OF BASE	SO YD	500	500
35800200	AGGREGATE BASE REPAIR	TON	50	50
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	74,376	74,376
40600300	AGGREGATE (PRIME COAT)	TON	157	157
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	4352	4352
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	3235	3235
40600990	TEMPORARY RAMP	SO YD	320	320
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	8704	8704
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	612	612
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	28424	28424
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	100	100
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3476	3476
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6

FILE NAME :	USER NAME : sparkgr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwwork\pwwork\sparkgr\0310810\06770-shi-500.dgn	DRAWN -	REVISED -	REVISED -						614	(146) RS-4	CASS	28	3
Default	PLOT SCALE = 100.0000' / 1" / 1/4"	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		
	PLOT DATE = Jun-05-2014 10:50:16AM	DATE -	REVISED -										