

ENTRANCES, SIDE ROADS & MAILBOX TURNOUTS				
LOCATION	TYPE OF ENTRANCE	HMA SURFACE REMOVAL BUTT JOINT	INCIDENTAL HMA SURFACING	TEMPORARY RAMPS
(STA. LT/ RT)	(SIDE RD, CE, PE, MB)	(SQ YD)	(TON)	(SQ YD)
1010+07.97 LT	PE/MB	48.41	9.49	
1011+69.25 RT	PE/MB	55.23	10.83	
1032+16.43 LT (FINN LANE)	SIDE ROAD	193.33	37.89	83.3
1033+02.16 RT	PE	37.35	7.32	
1035+23.35 LT	PE	33.17	6.50	
1035+95.41 RT	MB	33.06	6.48	
1036+05.24 LT	PE	40.76	7.99	
1038+66.99 RT	MB	11.47	2.25	
18+11.37 LT	PE	11.37	2.23	
19+85.04 RT	PE	39.24	7.69	
21+48.14 LT	PE	34.78	6.82	
23+83.49 RT	PE/MB	56.41	11.06	
24+90.03 RT	PE	42.24	8.28	
25+11.12 LT	PE	42.92	8.41	
26+92 LT	PE	33.69	6.60	
28+07 LT	PE	52.73	10.34	
30+87.27 RT (CHANDLERVILLE RD)	SIDE ROAD	218.05	42.74	61.11
45+91.81 LT	CE	34.80	6.82	
50+67.30 LT	CE	50.84	9.96	
61+26.44 RT	PE	42.62	8.35	
65++30.35 RT	PE/MB	50.29	9.86	
79+16.08 LT	PE/MB	48.67	9.54	
81+57.89 LT	PE	32.11	6.29	
94+29.79 RT	PE/MB	48.78	9.56	
95+63.97 RT	CE	33.77	6.62	
96+98.22 RT	CE	37.31	7.31	
101+64.35 LT	PE/MB	54.69	10.72	
110+77.86 LT (PALMERTON RD)	SIDE ROAD	51.70	10.13	13.3
123+35.94 RT	PE	60.37	11.83	
129+32 RT	PE	31.94	6.26	
133+78 LT	PE	64.71	12.68	
152+88 RT	CE	53.08	10.40	
156+54 RT	PE/MB	53.34	10.45	
166+57.63 RT	PE/MB	48.93	9.59	
187+26.80 RT	PE/MB	50.40	9.88	
232+49.36 RT	PE/MB	53.44	10.47	
236+51.35 LT (OLIVE BRANCH RD)	SIDE ROAD	67.85	13.30	13.3
236+57.50 RT (OLIVE BRANCH RD)	SIDE ROAD	37.18	7.29	13.3
242+52.91 RT	PE/MB	49.10	9.62	
251+62.66 LT	PE	39.20	7.68	
253+00.49 LT	PE	35.44	6.95	
253+11.83 RT	MB	32.67	6.40	
256+35.24 RT	MB	50.08	9.82	
289+45.77 RT (LOOKER LANE)	SIDE ROAD	47.70	9.35	22.2
293+71.27 LT	PE/MB	55.22	10.82	
297+19.81 RT	PE/MB	48.63	9.53	
307+44.16 LT	PE/MB	55.49	10.88	
307+40.04 RT	PE/MB	58.50	11.47	
312+96.57 RT	PE	41.15	8.07	
315+74.02 LT	PE/MB	53.49	10.48	
317+26.57 RT	PE	42.88	8.40	
324+34.57 LT	PE	37.36	7.32	
326+31.12 LT	PE	30.81	6.04	
330+91.01 LT	PE	42.82	8.39	
342+07.49 LT (GRANER ROAD)	SIDE ROAD	58.23	11.41	22.2
348+95.55 LT (REDBUD ROAD)	SIDE ROAD	87.10	17.07	33.3
357+67.18 RT	PE	42.69	8.37	
358+52.71 LT	PE	76.64	15.02	
358+96.41 RT	PE	54.25	10.63	
361+40.04 RT	PE	51.23	10.04	
362+80.70 RT	PE	37.52	7.35	
TOTAL		3119.23	611.37	262.01

ESTIMATED QUANTITIES FOR SIDEROADS / ENTRANCES*		
ITEM	QUANTITY	UNIT
PREPARATION OF BASE	500	SQ YD
AGGREGATE BASE REPAIR	50	TONS

* THESE QUANTITIES ARE ESTIMATED AND MAY BE INCREASED, DECREASED, OR DELETED AS DETERMINED BY THE ENGINEER WITHOUT ANY ADDITIONAL COMPENSATION TO THE CONTRACTOR.

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -
c:\pwwork\pwwork\sparksgw\100313810\0672770-sht-schedule.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = Jun-06-2014 10:51:29AM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
614	(146)RS-4	CASS	28	6
ILLINOIS FED. AID PROJECT			CONTRACT NO. 72F70	