

SUMMARY OF QUANTITIES				CONSTRUCTION CODE					
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SN 070-2018	SN 070-2018				
				RURAL	RURAL				
				0011	0021				
20200100	EARTH EXCAVATION	CU YD	310	310					
20400800	FURNISHED EXCAVATION	CU YD	160	160					
20700220	POROUS GRANULAR EMBANKMENT	CU YD	453	453					
25100630	EROSION CONTROL BLANKET	SQ YD	189	189					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25	25					
28000305	TEMPORARY DITCH CHECKS	FOOT	64	64					
28000400	PERIMETER EROSION BARRIER	FOOT	141	141					
28000500	INLET AND PIPE PROTECTION	EACH	1	1					
28100107	STONE RIPRAP, CLASS A4	SQ YD	138	138					
28200200	FILTER FABRIC	SQ YD	138	138					
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	354	354					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	71	71					
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	928	928					
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	8	8					
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	747	747					



JOB # 2223.1
 FILE NAME # 0774165-shr-rea.dgn
 PLOT SCALE # 28,0000 "/>

DESIGNED - NAK
 DRAWN - AJH
 CHECKED - NAK
 DATE - 8/25/2010
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
323	(142B) BR	MOUTRIE	35	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 74165	