

SUMMARY OF QUANTITIES				CONSTRUCTION CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SN 070-2018	SN 070-2018		
				RURAL 0011	RURAL 0021		
40600990	TEMPORARY RAMP	SQ YD	56	56			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	40	40			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	14	14			
44000100	PAVEMENT REMOVAL	SQ YD	134	134			
44004250	PAVED SHOULDER REMOVAL	SQ YD	225	225			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	307	307			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1			
50105220	PIPE CULVERT REMOVAL	FOOT	52	52			
50800105	REINFORCEMENT BARS	POUND	37,580	37,580			
50800515	BAR SPLICERS	EACH	142	142			
51500100	NAME PLATES	EACH	1	1			
54003000	CONCRETE BOX CULVERTS	CU YD	198.5	198.5			
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2	2			
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FOOT POSTS	FOOT	237.5	237.5			

* SPECIALTY ITEM



JOB # 2223.1
 FILE NAME * D774165-sht-sqa.dgn
 PLOT SCALE * 20.0000' / 1" =
 PLOT DATE * 8/11/2014

DESIGNED - NAK
 DRAWN - AJH
 CHECKED - NAK
 DATE - 8/25/2010

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE. 323	SECTION (142BY) BR	COUNTY MOULTRIE	TOTAL SHEETS 35	SHEET NO. 4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74165	