

RRPM SCHEDULE		RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER ( BRIDGE )	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	TEMPORARY RAISED PAVEMENT MARKER
STATION TO STATION	LENGTH ( FOOT )	( EACH )	( EACH )	( EACH )	( EACH )
230+00.0	232+28.0	228	3	0	3
232+58.0	239+07.0	649	0	8	0
239+37.0	243+25.0	388	5	0	5
TOTALS			8	8	8

PAVEMENT MARKING REMOVAL				PAVEMENT MARKING REMOVAL
	STATION TO STATION		LENGTH ( FOOT )	( SQ FT )
STAGE 1	229+28.0	231+25.0	C. L.	197
	240+00.0	242+37.0	C. L.	237
	231+25.0	240+40.0	EDGE	915
STAGE 2	230+87.0	232+23.0	EDGE	136
	239+36.0	240+82.0	EDGE	146
TOTAL				435.1

HMA PAVING SCHEDULE		HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70
STATION TO STATION	LENGTH ( FOOT )	( TON )	( TON )
230+00.0	232+23.0	223	73.7
239+37.0	239+43.0	6	1.2
239+43.0	242+02.0	259	56.1
242+02.0	243+25.0	123	28.2
TOTALS		159.2	126.9

WORK ZONE PAVEMENT MARKING REMOVAL			WORK ZONE PAVEMENT MARKING REMOVAL
	STATION TO STATION	LENGTH ( FOOT )	( SQ FT )
STAGE 1	229+88.0	242+22.0	1234
	231+25.0	240+40.0	915
STAGE 2	229+44.0	241+77.0	1233
	230+86.0	240+81.0	995
SHORT TERM	229+61.0	245+00.0	1539
	230+00.0	243+25.0	1325
TOTAL			1545.6

PAVEMENT REMOVAL SCHEDULE				PAVEMENT REMOVAL
STATION TO STATION	LENGTH ( FOOT )	WIDTH ( FOOT )	( SQ YD )	
232+22.5	232+28.5	16	24	
239+37.0	239+43.0	16	24	
TOTAL			85.3	