

BUTT JOINT SCHEDULE						HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP
STATION TO STATION		LENGTH (FOOT)	WIDTH (FOOT)	(SQ YD)	(SQ YD)		
307+75.0	308+80.0	105	32	373	12.2		
309+92.0	309+97.0	5.0	5	0	12.2		
311+72.0	311+77.0	5.0	5	0	12.2		
311+78.0	313+20.0	142	32	505	12.2		
TOTALS				878	48.8		

HMA SCHEDULE						BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70
STATION TO STATION		LENGTH (FOOT)	WIDTH (FOOT)	(POUND)	(TON)		
307+75.0	309+97.0	222	32	355	81.5		
311+72.0	313+20.0	148	32	237	42.4		
TOTALS				592	123.9		

PAVEMENT MARKING SCHEDULE					MODIFIED URETHANE PAVEMENT MARKING LINE 4"
STATION TO STATION			LENGTH (FOOT)	(FOOT)	
305+00.0	314+72.0	C. L.	972	243	
307+75.0	313+20.0	EDGE	545	1090	
TOTAL			1333		

YELLOW
WHITE

TEMPORARY TRAFFIC CONTROL								TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY-REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (FULLY-REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
	STATION TO STATION		(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)					
STAGE 1	309+20.0	313+06.7	388	0	1	1	0	0					
STAGE 2	310+22.0	312+87.0	0	263	0	0	1	1					
TOTALS			388	263	1	1	1	1					

REMOVAL SCHEDULE						PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL
STATION TO STATION		LENGTH (FOOT)	WIDTH (FOOT)	(SQ YD)	(SQ YD)		
309+91.0	310+07.0	16	32	57	0.0		
311+63.0	311+79.0	16	32	57	0.0		
312+53.0	313+20.0	67	1.5	0	22.3		
TOTAL				114	22.3		

PAVEMENT MARKING REMOVAL					PAVEMENT MARKING REMOVAL
	STATION TO STATION			LENGTH (FOOT)	(SQ FT)
STAGE 1	305+00.0	307+00.0	C. L.	200	16.7
	313+00.0	314+72.0	EDGE	172	14.3
	306+84.0	313+20.0	EDGE	636	212.0
STAGE 2	307+78.0	309+97.0	EDGE	219	73.0
	311+72.0	313+20.0	EDGE	148	49.3
TOTAL				365.3	

WIDENING SCHEDULE						EARTH EXCAVATION (WIDENING)	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"
	STATION TO STATION		LENGTH (FOOT)	WIDTH (FOOT)	(CU YD)	(SQ YD)	
LT	312+53.0	313+20.0	67	5	10	37.2	
RT	312+53.0	313+20.0	67	5	10	37.2	
TOTALS				21	74.4		

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
c:\pw\work\p\dot\steffenmk\d0283030\074365-sht-sch.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 8/15/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES			
SCALE:	SHEET	OF	SHEETS
	STA.	TO	STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
823	(22BR2)BR	Wayne	34	8
CONTRACT NO. 74365			ILLINOIS FED. AID PROJECT	