

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80/20 FED / STATE CONSTRUCTION CODE	
				URBAN	
				ROADWAY 0004	BRIDGE 0014 S. N. 058-0050
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100	
35400520	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 12"	SQ YD	58	58	
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	97481	97481	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	6065	6065	
40600990	TEMPORARY RAMP	SQ YD	1848	1848	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	9098	9098	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	39	39	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3034	3034	
42400800	DETECTABLE WARNINGS	SQ FT	302	302	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	108312	108312	
44000300	CURB REMOVAL	FOOT	180	180	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1305	1305	
44000600	SIDEWALK REMOVAL	SQ FT	2091	2091	
44201385	CLASS C PATCHES, TYPE I, 13 INCH	SQ YD	112	112	

• SPECIALTY ITEM

FILE NAME =	USER NAME = jbenning	DESIGNED - CAS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES FAP 320 (IL 121)</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
\\NDOT\6888 - 07 Ver Ver\Mark Order 3	IL 121 Resurfacing\CRDD\Civil\0774624\shc-5	DRAWN - DLB	REVISED -					320	1126XRS-2.135RS-1	MACON	119	4
Default	PLOT SCALE = 1/8" = 1' / in.	CHECKED - JMB	REVISED -		SCALE:	SHEET 1	OF 9 SHEETS	STA.	TO STA.	CONTRACT NO. 74624		
	PLOT DATE = 8/27/2014	DATE - 8/13/14	REVISED -		(ILLINOIS) FED. AID PROJECT							