

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80/20 FED / STATE CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004	0014
				S. N. 058-0050	
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	2	2	
X4060995	TEMPORARY RAMP, SPECIAL	SQ YD	619	619	
X4240430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	681	681	
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	4715	4715	
X4402805	ISLAND REMOVAL	SQ FT	579	579	
X4403300	CONCRETE MEDIAN REMOVAL	SQ FT	110	110	
X6060060	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.06 (SPECIAL)	FOOT	79	79	
X6061700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL)	FOOT	525	525	
X7010228	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601, SPECIAL	L SUM	1	1	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	28	
* X7830060	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	1769	1769	
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	25432	25432	
* X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	18935	18935	
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	2569	2569	

\* SPECIALTY ITEM

FILE NAME =	USER NAME = jboering	DESIGNED - CAS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES FAP 320 (IL 121)</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
IN\DOT\6000 - 07 Van Ver-Work Order 3	IL 121 Resurfacing\CADD\Civil\0774624-shc-5	DRAWN - DLB	REVISED -		SCALE:	SHEET 8	OF 9 SHEETS	STA.	TO STA.	320	(126XRS-2,135RS-1)	MACON	119	7a
Default	PLOT SCALE = 100.0000' / 1"	CHECKED - JMB	REVISED -		CONTRACT NO. 74624									
	PLOT DATE = 8/27/2014	DATE - 8/13/14	REVISED -		ILLINOIS FED. AID PROJECT									