

**PAVEMENT MARKING SCHEDULE**

LOCATION	THERMOPLASTIC PAVEMENT MARKING LINE - 4" YELLOW SOLID (LF)	THERMOPLASTIC PAVEMENT MARKING LINE - 4" YELLOW SKIP DASH (LF)	THERMOPLASTIC PAVEMENT MARKING LINE - 4" YELLOW DOUBLE (LF)	THERMOPLASTIC PAVEMENT MARKING LINE - 6" WHITE SOLID (LF)	THERMOPLASTIC PAVEMENT MARKING LINE - 6" WHITE SKIP DASH (LF)	THERMOPLASTIC PAVEMENT MARKING LINE - 6" WHITE DOTTED (LF)	THERMOPLASTIC PAVEMENT MARKING LINE - 8" WHITE SOLID (LF)	THERMOPLASTIC PAVEMENT MARKING LINE - 12" WHITE SOLID (LF)	THERMOPLASTIC PAVEMENT MARKING LINE - 24" WHITE SOLID (LF)	THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS WHITE (SF)	PREFORMED PLASTIC PAVEMENT MARKING TYPE B-4" YELLOW SOLID (LF)	PREFORMED PLASTIC PAVEMENT MARKING TYPE B-6" WHITE SKIP DASH (LF)	PREFORMED PLASTIC PAVEMENT MARKING TYPE B-12" WHITE SOLID (LF)	PRISMATIC CURB REFLECTORS CRYSTAL (EACH)	PRISMATIC CURB REFLECTORS AMBER (EACH)	RAISED REFLECTIVE PAVEMENT MARKERS CRYSTAL (EACH)	RAISED REFLECTIVE PAVEMENT MARKERS AMBER (EACH)
UNIVERSITY TO PERSHING CT.	2403			1253	560	299	332	998	220	202.4			244	33	102	56	
PERSHING CT. TO MONROE	3092			825	870	234	0	506	154	184.8					151	70	
MONROE TO MAIN ST.	3537			872	900	255	416	554	184	158.4	339	100		10	152	76	
MAIN ST. TO MARTIN LUTHER KING	3190		120	2021	910	307	724	494	365	396.6				35	124	95	
MARTIN LUTHER KING TO VICKI DR.	3508		66	754	860	213	312	481	343	140.8					127	68	
VICKI DR TO WOODFORD AVE.	3204			2092	830	532	474	165	511	352.0				20	148	108	
WOODFORD AVE. TO STA 77+00	4903	1070		390	1230	91	311	81	166	333.6					26	69	107
SUB-TOTALS	23837	1070	186	8207	6160	1931	2569	3279	1943	1769	339	100	244	98	830	542	107
TOTALS		25093			16298		2569	3279	1943	1769	339	100	244		928		649

**PCC SIDEWALK 5" SCHEDULE**

STATION	OFFSET	AREA (SF)
1020+41	53 LT	112.00
1020+32	44 RT	123.00
1021+03	52 LT	339.00
1021+10	48 RT	155.00
1032+89	51 LT	177.00
1032+91	10 LT	40.00
1032+93	40 RT	127.00
1033+55	42 RT	146.00
1033+61	44 LT	162.00
1051+16	57 RT	34.00
1051+19	57 LT	123.00
1052+52	63 RT	68.00
54+82	80 RT	128.00
54+93	46 RT	60.00
54+98	77 LT	140.00
54+95	0 LT	212.00
60+81	4 RT	137.00
61+03	73 LT	341.00
61+03	67 RT	136.00
19+09	37 RT	103.00
19+15	51 LT	112.00

Total	2975.00
<b>Rounded</b>	<b>2975</b>

**PAVING SCHEDULE**

LOCATION	LEVELING BINDER (MACHINE METHOD), N90 (TONS)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX "D", N90 (TONS)	BITUMINOUS MATERIALS (PRIME COAT) 2 APPLICATIONS (POUND)	HOT-MIX ASPHALT SURFACE REMOVAL 2-1/2" (SQ YD)
UNIVERSITY TO PERSHING CT.	624.5	936.7	10036.0	11151.1
PERSHING CT. TO MONROE	847.4	1271.0	13618.3	15131.4
MONROE TO MAIN ST.	880.3	1320.5	14147.7	15719.7
MAIN ST. TO MARTIN LUTHER KING	938.4	1407.7	15082.1	16757.9
MARTIN LUTHER KING TO VICKI DR	790.1	1185.1	12698.0	14108.9
VICKI DR TO WOODFORD AVE.	979.0	1468.5	15734.0	17482.2
WOODFORD AVE. TO STA 77+00	1005.8	1508.7	16164.4	17960.4
TOTALS	6065	9098	97481	108312

**MANHOLES TO BE ADJUSTED SCHEDULE**

STATION	LOCATION	O/S	QUADRANT	QUANTITY (EA)
1051+21.54	MACARTHUR	67.09 LT	NW	1
Total				1

**TEMPORARY RAMP, SPECIAL SCHEDULE**

STATION	NO. OF DRIVEWAYS	AREA (SQ FT)	AREA (SQ YD)
UNIVERSITY TO PERSHING CT	10	480.00	53.33
PERSHING CT TO MONROE	16	768.00	85.33
MONROE TO MAIN	13	624.00	69.33
MAIN TO MLK	19	912.00	101.33
MLK TO VICKI DR	8	384.00	42.67
VICKI DR TO WOODFORD AVE	19	912.00	101.33
WOODFORD AVE TO STA 77+00	31	1488.00	165.33
TOTAL		618.67	
ROUNDED		<b>619</b>	

**DETECTABLE WARNINGS SCHEDULE**

STATION	OFFSET	AREA (SF)
1020+41	53 LT	16.00
1020+32	46 RT	22.00
1021+03	52 LT	10.00
1021+10	48 RT	13.00
1032+89	54 LT	10.00
1032+91	11 LT	10.00
1032+91	7 LT	10.00
1032+93	40 RT	10.00
1033+55	42 RT	10.00
1033+67	42 LT	10.00
1051+16	57 RT	10.00
1051+19	57 LT	10.00
1052+52	63 RT	11.00
54+84	83 RT	10.00
54+99	80 LT	18.00
54+93	46 RT	10.00
54+93	51 RT	10.00
54+94	16 RT	10.00
54+95	17 LT	10.00
60+82	17 RT	10.00
60+83	4 LT	10.00
61+03	72 LT	10.00
61+03	68 RT	10.00
19+09	37 RT	10.00
19+15	51 LT	12.00
31+54	36 LT	10.00
31+49	46 RT	10.00
Total		302.00
<b>Rounded</b>		<b>302</b>

**TEMPORARY RAMP SCHEDULE**

STATION	OFFSET	SIZE	AREA (SF)	AREA (SY)
1021+00	LT & RT	8.33 X 98	816.34	90.70
OAKLAND AVE NORTH	LT	8.33 X 51	424.83	47.20
OAKLAND AVE SOUTH	RT	8.33 X 70	583.10	64.79
PERSHING CT	LT	8.33 X 56	466.48	51.83
LYNETTE CT	LT	8.33 X 54	449.82	49.98
BARNES DR	LT	8.33 X 53	441.49	49.05
MONTEZ DR	LT	8.33 X 55	458.15	50.91
MACARTHUR RD	LT	8.33 X 85	708.05	78.67
MONROE ST	RT	8.33 X 106	882.98	98.11
FAIR OAKS DR.	LT	8.33 X 40	333.20	37.02
GREENRIDGE DR	LT	8.33 X 64	533.12	59.24
WEST END BRIDGE	LT & RT	8.33 X 68	566.44	62.94
EAST END BRIDGE	LT & RT	8.33 X 68	566.44	62.94
MAIN ST	LT	8.33 X 56	466.48	51.83
MAIN ST	RT	8.33 X 59	491.47	54.61
WATER ST	LT	8.33 X 52	433.16	48.13
WATER ST	RT	8.33 X 65	541.45	60.16
MLK AVE	LT	8.33 X 76	633.08	70.34
MLK AVE	RT	8.33 X 76	633.08	70.34
BRETT AVE	LT	8.33 X 55	458.15	50.91
VICKI DR	LT	8.33 X 42	349.86	38.87
VICKI DR	RT	8.33 X 50	416.50	46.28
JASPER ST	RT	8.33 X 78	649.74	72.19
CHARLES ST	LT	8.33 X 106	882.98	98.11
WOODFORD AVE	LT	8.33 X 75	624.75	69.42
WOODFORD AVE	RT	8.33 X 73	608.09	67.57
KANDY LANE	LT	8.33 X 24	199.92	22.21
GRAND PRIX DR	LT	8.33 X 180	1499.40	166.60
75+52	RT	8.33 X 24	199.92	22.21
76+06	LT	8.33 X 37	308.21	34.25
Total			16626.68	1847.41
<b>Rounded</b>			<b>16627</b>	<b>1848</b>