

SCHEDULE OF QUANTITIES

STRUCTURE NUMBER	LOCATION	STRUCTURE LENGTH FEET	STRUCTURE WIDTH FEET	MILLING/PAVING LENGTH FEET	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH SO YD	BITUMINOUS MATERIALS (PRIME COAT) POUND	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 TON	THERMOPLASTIC PAVEMENT MARKING - LINE 6" FOOT	THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT	GROOVING FOR RECESSED PAVEMENT MARKING 5" FOOT	GROOVING FOR RECESSED PAVEMENT MARKING 7" FOOT	SHORT-TERM PAVEMENT MARKING FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SO FT	RAISED REFLECTIVE PAVEMENT MARKER EACH
COLES COUNTY														
SN 015-0003	I-57 (SB)	209	33	217	796	358	89	54	434	434	54	39	13	5
SN 015-0004	I-57 (NB)	209	33	217	796	358	89	54	434	434	54	39	13	5
SN 015-0005	I-57 (NB)	238	48	246	1312	590	147	62	492	492	62	44	15	6
SN 015-0006	I-57 (SB)	238	48	246	1312	590	147	62	492	492	62	44	15	6
COLES COUNTY TOTALS					4215	1897	472	232	1852	1852	232	167	55	23
CUMBERLAND COUNTY														
018-0001	I-57 (SB)	292	36	300	1200	540	101	75	600	600	75	54	18	8
018-0002	I-57 (NB)	292	36	300	1200	540	101	75	600	600	75	54	18	8
018-0003	I-57 (SB)	138	39	146	633	285	53	37	292	292	37	26	9	4
018-0004	I-57 (NB)	138	39	146	633	285	53	37	292	292	37	26	9	4
CUMBERLAND CO. TOTALS					3665	1649	308	223	1784	1784	223	161	53	22
PROJECT TOTALS					7881	3546	780	455	3636	3636	455	327	108	45

• COLES, CUMBERLAND

FILE NAME -	USER NAME -	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pvc\work\101\dot\1\work\101\dot\1\74677	4677-ahs-sch.dgn	DRAWN -	REVISED -					57	D7 BRIDGE REPAIRS 2015-1		8	4
Default	PLOT SCALE - 1/8"=1'-0"	CHECKED -	REVISED -		SCALE: N/A		SHEET 1	OF 1	SHEETS	STA.	TQ STA.	CONTRACT NO. 74677
	PLOT DATE - 10/3/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							