

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY	
				0004	RURAL
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	10091	10091	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	11605	11605	
28000305	TEMPORARY DITCH CHECKS	FOOT	12663	12663	
28000315	AGGREGATE DITCH CHECKS	TON	830	830	
28000400	PERIMETER EROSION BARRIER	FOOT	27037	27037	
28000500	INLET AND PIPE PROTECTION	EACH	111	111	
28100107	STONE RIPRAP, CLASS A4	SQ YD	2564	2564	
28100109	STONE RIPRAP, CLASS A5	SQ YD	2280	2280	
28200200	FILTER FABRIC	SQ YD	9353	9353	
28300400	AGGREGATE DITCH	TON	3157	3157	
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	586	586	
31101600	SUBBASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	64602	64602	
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	5411	5411	
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	613	613	

• FAS 752/FAS 749

FILE NAME =	USER NAME = harbaughrd	DESIGNED -	REVISED -
et:\pwork\pwork\harbaughrd\0130185\d876789-sht-500.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = 8/22/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 2 OF 14 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	101-2RS-1	JERSEY	438	4
			CONTRACT NO. 76789	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		