

FILE NAME = S:\Projects\085-022B-VHY IL 3_Cross\Drawings\CADD_Sheets\08576789-st-schedule.dgn

ENTRANCE CULVERT SCHEDULE																		
LOCATION		EXISTING CULVERT			PIPE CULVERT REMOVAL	REMOVAL OF EXISTING STRUCTURE	PIPE CULVERTS									PRECAST REINFORCED CONCRETE FLARED END SECTIONS		
STATION	SIDE	MATERIAL	SIZE	HEADWALL			CLASS A, TYPE 1	CLASS D, TYPE 1			CLASS D, TYPE 2			30"	36"			
	LT/RT		INCHES	NUMBER	FOOT	30"	36"	15"	18"	24"	30"	15"	18"	48"	30"	36"		
						FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH		
335+79.00	LT	CMP	12	0	31.18					44								
336+98.00	RT	CMP	12	2	27.48			44										
339+76.45	LT	CMP	15	2	24.89					48								
341+62.00	RT	CMP	15	0	37.06	52									2			
341+62.00	LT	CMP	15	2	26.04		62									2		
351+86.00	LT	CMP	15	0	21.66			49										
359+60.00	RT							46										
370+15.00	RT	CMP	15	0	18			53										
374+95.50	LT							36										
380+17.00	RT	BOX CULV	1' X1'	2				45										
382+19.00	RT	CMP	12	2	22.08			40										
389+37.00	LT							40										
391+50.00	LT	CMP	12	2	24.09			40										
392+60.50	RT	CMP	15	2	28.79			40										
396+17.00	LT	CMP	15	2	18.91			34										
407+30.00	LT											66						
407+83.00	RT							53										
416+13.00	RT								47									
417+10.00	RT							47										
420+35.00	RT	CMP	12	2	30.29			52										
421+17.00	LT							67										
421+72.00	RT	CMP	15	2	24.46			44										
422+98.00	LT							55										
NEWBERN RD.																		
13+21.69	LT	CMP	12	2	18.69			36										
TOTAL					1888.95	INFORMATION		110	103	2615	364	696	116	66	76	100	4	2
ROUNDED					1889	ONLY												

NOTES: (A) NOT A TOTAL QUANTITY, SEE CROSS ROAD CULVERT SCHEDULE (A)
 (B) NOT A TOTAL QUANTITY, SEE STORM SEWER SCHEDULE (B)
 • ONE CULVERT GOES UNDER TWO ENTRANCES, COMBINE LENGTHS FOR TOTAL LENGTH OF CULVERT

STORM SEWER SCHEDULE												
LOCATION						TRENCH BACKFILL	STORM SEWER, CLASS A, TYPE 1		MANHOLES, TYPE A		PRECAST REINFORCED CONCRETE FLARED END SECTIONS	
STRUCTURE NUMBER	STATION	OFFSET	SIDE	FROM STRUCTURE	TO STRUCTURE		18 INCH	36 INCH	5' DIA., TYPE 1 FRAME, CLOSED LID	7' DIA., TYPE 8 GRATE	18 INCH	36 INCH
						SO YD	FOOT	FOOT	EACH	EACH	EACH	EACH
DRAINAGE STRUCTURES												
1	184+57.58	27.3	RT								1	
2	184+81.48	24.5	RT							1		
3	185+49.80	33.6	RT									1
4	184+81.48	22.0	LT						1			
5	184+71.37	40.2	LT									1
STORM SEWERS												
				1	2		15					
				3	2			58				
				2	4	22		42				
				4	5			11				
TOTALS						22	15	111	1	1	1	2

NOTES: (A) NOT A TOTAL QUANTITY SEE CROSS ROAD CULVERT SCHEDULE (A)
 (B) NOT A TOTAL QUANTITY SEE ENTRANCE CULVERT SCHEDULE (B)



USER NAME = l.jackson	DESIGNED - ACM	REVISED -
MODEL NAME = Schedule 06	DRAWN - EDW	REVISED -
PLOT SCALE = 2.0000' / 1" =	CHECKED - LWJ	REVISED -
PLOT DATE = 8/22/2014	DATE - 8-11-14	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES FAS ROUTE 749/752 (IL RTE 3)		
SCALE:	SHEET 6 OF 26 SHEETS	

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
• 749/752	101-2RS-1	JERSEY	438	27
CONTRACT NO. 76789			ILLINOIS FED. AID PROJECT	