

FILE NAME = S:\Projects\082B-VH\IL_3_CrossRoad\CADD_Sheets\082B-VH-IL_3-CrossRoad-Schedule.dgn

CROSS ROAD CULVERT SCHEDULE																											
LOCATION		SIZE		TYPE	PIPE CULVERT REMOVAL	REMOVAL OF EXISTING STRUCTURE			FILLING EXISTING CULVERT	CONCRETE HEADWALL REMOVAL	PRECAST CONCRETE BOX CULVERT		BOX CULVERT END SECTIONS	PIPE CULVERT, CLASS A, TYPE 1			PRECAST REINFORCED CONCRETE FLARED END SECTIONS		TRENCH BACKFILL	TRAFFIC CONTROL AND PROTECTION STANDARD 701321 (SPECIAL)	BOX CULVERTS TO BE CLEANED						
CULVERT NUMBER	STATION	WIDTH	HEIGHT			ENTIRE CULVERT	CULVERT EXTENSION	DROP BOX			CU YD	EACH		4' X3'	5' X3'	EACH	18 INCH	24 INCH				30 INCH	18 INCH	24 INCH	CU YDS	EACH	EACH
		FOOT	FOOT											FOOT	FOOT		FOOT	FOOT				FOOT	FOOT	FOOT			
IL 3																											
EXISTING	133+38.12	2	2	REMOVAL	16.5	1												27.4									
1	133+42.53	30"		REPLACEMENT										56		2	15.9										
2	149+43.87	4	4	EXTENSION																1							
3	157+19.02	3	3 & 7	EXTENSION																1							
4	170+83.60	4	3	REPLACEMENT						60		2								1							
EXISTING	171+01.23	3	3	ABANDON				22.1	2											1							
5	174+73.19	10	10	EXTENSION																1							
EXISTING	184+69.85	2	1.5	ABANDON				5.9	1											1							
6	184+81.48	36"		REPLACEMENT																1							
7	191+33.46	2	1.5	EXTENSION																1							
8	217+14.99	8	8	EXTENSION																1							
9	234+34.89	10	8	EXTENSION																1							
10	242+68.86	2.5	2.5	EXTENSION																1							
11	275+57.76	2	1.5	EXTENSION																1							
12	283+25.00	4	2	REPLACEMENT																1							
EXISTING	284+17.72	2	1.5	ABANDON				3.8	2											1							
13	287+70.68	4	3	REPLACEMENT						78		2								1							
EXISTING	287+75.90	2	2	REMOVAL		13														1							
14	290+69.78	2	1.5	EXTENSION																1							
15	300+01.62	6	6	EXTENSION																1							
EXISTING	314+36.20	2	2	ABANDON				8.9	2											1							
16	314+85.11	5	3	REPLACEMENT							48	2								1							
17	321+53.05	2	1.5	EXTENSION																1							
18	326+74.64	2	1.5	EXTENSION																1							
19	335+54.73	2	1.5	EXTENSION																1							
20	343+84.53	2	2	EXTENSION																1							
21	349+98.07	10	10	EXTENSION																1							
22	354+11.67	3	3	EXTENSION																1							
23	370+51.35	3	3	EXTENSION																1							
24	371+04.61	3	3	EXTENSION																1							
25	379+24.68	2	1.5	EXTENSION																1							
26	387+50.59	2	1.5	EXTENSION																1							
27	397+30.51	2	1.5	EXTENSION																1							
28	405+67.37	10	10	EXTENSION																1							
29	411+43.66	7	7	EXTENSION																1							
OTTERVILLE ROAD																											
30	20+92.13	18"		REPLACEMENT	45.4									48		2				12.4							
SALEM ROAD																											
31	40+33.96	24"		REPLACEMENT	37.7										90		2			10.4							
NEWBERN ROAD																											
32	50+40.50	3	3	REPLACEMENT		22														SEE STRUCTURE PLANS							
CEMETERY ROAD																											
EXISTING	60+30.85	2	1.5	REMOVAL		21																					
33	60+40.51	4	2	REPLACEMENT																SEE STRUCTURE PLANS							
TOTALS					99.6			40.7	7	138	48			48	90	56	2	4	66.1	11	8						
ROUNDING					(A)			41											67	(B)							

NOTES: (A) NOT A TOTAL QUANTITY SEE ENTRANCE CULVERT SCHEDULE
 (B) NOT A TOTAL QUANTITY SEE STORM SEWER SCHEDULE



USER NAME = ljackson	DESIGNED - ACM	REVISED -
MODEL NAME = Schedule 07	DRAWN - EDW	REVISED -
PLOT SCALE = 2.0000' / 1" =	CHECKED - LWJ	REVISED -
PLOT DATE = 8/22/2014	DATE - 8-11-14	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES	
FAS ROUTE 749/752 (IL RTE 3)	
SCALE:	SHEET 7 OF 26 SHEETS

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	101-2RS-1	JERSEY	438	28
• 749/752		CONTRACT NO. 76789		
ILLINOIS FED. AID PROJECT				