

PAVEMENT MARKING SCHEDULE															
LOCATION		LENGTH	SIDE ROAD OMISSIONS	SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING				WORK ZONE PAVEMENT MARKING	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING				RAISED REFLECTIVE PAVEMENT	
					4 INCH LINE		24 INCH LINE			4 INCH LINE		24 INCH LINE			
STATION	TO	STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	FOOT	EACH	
99+06.67	TO	101+39.00	232.33			232.33					232.33				
101+39.00	TO	114+50.00	1311.00	133	119.2	2489.0	222.5	1732	1520.9	2489.0	222.5	1732.0		17	
114+50.00	TO	129+50.00	1500.00		136.4	3000.0	375.0	922.14	1477.8	3000.0	375.0	922.1		19	
129+50.00	TO	142+50.00	1300.00	180	118.2	2420.0	142.5	2030	1570.2	2420.0	142.5	2030.0		17	
142+50.00	TO	157+50.00	1500.00		136.4	3000.0	375.0	785	1432.1	3000.0	375.0	785.0		19	
157+50.00	TO	172+00.00	1450.00		131.8	2900.0	325.0	1320	1558.9	2900.0	325.0	1320.0		19	
172+00.00	TO	187+00.00	1500.00	171	136.4	2829.0	215.0	2140	1773.5	2829.0	215.0	2140.0		19	
187+00.00	TO	202+00.00	1500.00		136.4	3000.0	200.0	2200	1845.5	3000.0	200.0	2200.0		19	
202+00.00	TO	217+00.00	1500.00		136.4	3000.0	375.0	845	1452.1	3000.0	375.0	845.0		19	
217+00.00	TO	232+00.00	1500.00		136.4	3000.0	375.0	1390	1633.8	3000.0	375.0	1390.0		19	
232+00.00	TO	247+00.00	1500.00		136.4	3000.0	375.0	310	1273.8	3000.0	375.0	310.0		19	
247+00.00	TO	262+00.00	1500.00	200	136.4	2800.0	375.0	0	1103.8	2800.0	375.0	0.0		19	
262+00.00	TO	277+00.00	1500.00	177	136.4	2823.0	375.0	0	1111.5	2823.0	375.0	0.0		19	
277+00.00	TO	292+00.00	1500.00		136.4	3000.0	375.0	910	1473.8	3000.0	375.0	910.0		19	
292+00.00	TO	307+00.00	1500.00		136.4	3000.0	52.5	2790	1993.0	3000.0	52.5	2790.0		19	
307+00.00	TO	322+00.00	1500.00		136.4	3000.0	0.0	3000	2045.5	3000.0	0.0	3000.0		19	
322+00.00	TO	337+00.00	1500.00		136.4	3000.0	137.5	2450	1908.0	3000.0	137.5	2450.0		19	
337+00.00	TO	352+00.00	1500.00		136.4	3000.0	375.0	420	1310.5	3000.0	375.0	420.0		19	
352+00.00	TO	367+00.00	1500.00	219	136.4	2781.0	287.5	1796	1667.0	2781.0	287.5	1796.0		19	
367+00.00	TO	382+00.00	1500.00		136.4	3000.0	0.0	3000	2045.5	3000.0	0.0	3000.0		19	
382+00.00	TO	397+00.00	1500.00		136.4	3000.0	0.0	3000	2045.5	3000.0	0.0	3000.0		19	
397+00.00	TO	412+00.00	1500.00		136.4	3000.0	366.3	1457	1653.2	3000.0	366.3	1457.0		19	
412+00.00	TO	424+51.50	1251.50	74	113.8	2578.7	312.9	1037	1347.4	2578.7	312.9	1037.0	50	16	
SUB-TOTAL					2937.5	63853.0	5636.6	33534.14	50	35243.0	63853.0	5636.6	33534.1	50	411
COMBINE 4 INCH LINES								103023.8					103023.8		
ROUNDED					2938			103024	50	35243			103024	50	411
SIDE ROADS															
CROXFORD ROAD															
10+12.30	TO	10+90.00							37					37	
OTTERVILLE ROAD															
20+13.37	TO	21+65.00	151.6		13.78	377.76	40		32	143.85	377.76	40		32	
ELSAH ROAD															
30+12.00	TO	31+25.00							63					63	
SALEM ROAD															
40+12.00	TO	41+45.00							47					47	
NEWBERN ROAD															
50+12.00	TO	51+15.00							30					30	
CEMETERY ROAD															
60+12.00	TO	61+10.00							23					23	
SUB-TOTAL					13.78	377.76	40.00		232.00	143.85	377.76	40.00		232.00	
COMBINE 4 INCH LINES							417.8				417.8				
ROUNDED							418		232		418			232	
TOTAL					2938		103442		282	35243		103442		282	411

(A) NOT A TOTAL QUANTITY, SEE TRAFFIC CONTROL SCHEDULE

FILE NAME = S:\Projects\0828-VH\IL_3_Cref\cm\lgm\CADD_Sheets\0876789-st-schedule.dgn



USER NAME = ljackson	DESIGNED - ACM	REVISED -
MODEL NAME = Schedule 26	DRAWN - EDW	REVISED -
PLOT SCALE = 2.0000' / in.	CHECKED - LWJ	REVISED -
PLOT DATE = 8/22/2014	DATE - 8-11-14	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES	
FAS ROUTE 749/752 (IL RTE 3)	
SCALE:	SHEET 26 OF 26 SHEETS

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	101-2RS-1	JERSEY	438	47
• 749/752		CONTRACT NO. 76789		
ILLINOIS FED. AID PROJECT				