

PAVEMENT MARKING SCHEDULE

STA	TO	STA	THERMOPLASTIC				PREFORMED PLASTIC	SHORT TERM PVMT MARK FT	TEMP PVMT MARK 4" FT	TEMP PVMT MARK 8" FT	TEMP PVMT MARK 24"* FT	WORK ZONE PVT MK REM SQ FT	RAISED REFL PVT MARK EACH	RAISED REFL PVT MKR REM EACH	DELINEATORS EACH	SHLDR RUMBLE STRIPS 16" FT
			LINE - 4"		LINE - 8"	LINE-24"	LINE - 6"									
			WHITE SOLID FT	YELLOW SOLID FT	WHITE SOLID FT	WHITE SOLID* FT	WHITE SKIP FT									
NB																
STA 105+21.80	TO STA	1215+41.25	11020	11020		18	2755	3967	22040		18	8706	138	138	28	22039
EON STA 215+41.25	BK=STA1215+44.50	AH														
STA 215+44.50	TO STA	1238+93.67	1381	2350	403		587	846	3731	403		1795	30	30	3	3731
STA 238+93.67	TO STA	1240+47.59	GAP													
STA 240+47.59	TO STA	1251+30.97	1084	1084			271	390	2168			853	14	14	3	2167
STA 251+30.97	TO STA	1253+43.97	GAP													
STA 253+43.97	TO STA	1374+45.00	12102	12102			3025	4356	24204			9521	152	152	30	24202
SB																
STA 105+21.80	TO STA	1215+41.25	11020	11020		18	2755	3967	22040		18	8706	138	138	28	22039
EON STA 215+41.25	BK=STA1215+44.50	AH														
STA 215+44.50	TO STA	1239+17.13	816	2373	383		593	854	3189	383		1604	30	30	2	3189
STA 239+17.13	TO STA	1240+71.05	GAP													
STA 240+71.05	TO STA	1252+11.45	1141	1141			285	411	2282			898	15	15	3	2281
STA 252+11.45	TO STA	1254+24.45	GAP													
STA 254+24.45	TO STA	1374+45.00	12021	12021			3005	4327	24042			9457	151	151	30	24041
RAMPS																
STA 88+78.90	TO STA	117+69.93	A	2892	1784	145	70	215	4676	145		1727			28	
STA 240+59.82	TO STA	263+84.70	B	2325	1692	383		161	4017	383		1648	61	61	27	
STA 318+83.62	TO STA	338+78.30	C	1995	1303	404		132	3298	404		1413	65	65	20	
STA 427+74.70	TO STA	447+41.44	D	1967	904	100	39	130	2871	100		1068			21	
RURAL TOTALS			59764	58794	1818	36	13386	19756	118558	1818	36	47396	794	794	222	103689

118558

*STATE POLICE SPEED MEASUREMENTS MUST BE PLACED EXACT LOCATION OF THE EXISTING MARKINGS