CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0040					
25100900	TURF REINFORCEMENT MAT	SQ YD	270	270					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2050	2050					
28000305	TEMPORARY DITCH CHECKS	FOOT	90	90					
28000400	PERIMETER EROSION BARRIER	FOOT	1550	1550					
28000500	INLET AND PIPE PROTECTION	EACH	3	3					
28100725	STONE DUMPED RIPRAP, CLASS B3	SQ YD	83	83					
28200200	FILTER FABRIC	SQ YD	83	83					
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	1037	1037					
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	190	190					
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	40	40					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	123	123					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	289	289					
42400800	DETECTABLE WARNINGS	SQ FT	20	20					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	221	221					

14

FILE NAME = U:\IFiles\V18023\Work Order 3 MO Ave PhZ\C009 Sheets\0876C99-sht-summary.dgn

KLINGNER & ASSOCIATES, P.C.
Engineers · Architects · Surveyors

USER NAME = seb	DESIGNED - seb	REVISED -
	DRAWN - seb	REVISED -
PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 9/29/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
MISSOURI AVENUE DEEP WELL FACILITY

SCALE: NONE | SHEET 2 OF 10 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-4T-1	ST. CLAIR	185	5

CONTRACT NO. 76G99

ILLINOIS FED. AID PROJECT